

# **KWONEESUM DAM DRAFT FINAL REMOVAL DESIGN** SKAMANIA COUNTY, WASHINGTON June 4, 2021

34 - KWONEESUM RESERVOIR AND DAM - DAM REMOVAL AREA

- 35 KWONEESUM RESERVOIR AND DAM DAM REMOVAL AREA
- 36 KWONEESUM RESERVOIR AND DAM CONTAINMENT ROAD PLAN
- 38 KWONFESUM RESERVOIR AND DAM CONTAINMENT ROAD
- 39 KWONEESUM RESERVOIR AND DAM-NORTH TRIB. GRADING PLAN 77 TYPICAL DETAILS
- 40 KWONFESUM RESERVOIR AND DAM-NORTH TRIB LARGE WOOD 41 - KWONEESUM RESERVOIR AND DAM - NORTH TRIB. GRADING
- 42 KWONEESUM RESERVOIR AND DAM NORTH TRIB. GRADING
- 43 KWONEESUM RESERVOIR AND DAM -EAST TRIB. GRADING PLAN AND
- 44 KWONEESUM RESERVOIR AND DAM -EAST TRIB. LARGE WOOD 45 - KWONEESUM RESERVOIR AND DAM – EAST TRIB. GRADING
- 46 KWONEESUM RESERVOIR AND DAM EAST TRIB. GRADING
- 47 KWONEESUM RESERVOIR AND DAM -WEST TRIB. GRADING PLAN AND
- 48 KWONEESUM RESERVOIR AND DAM -WEST TRIB. LARGE WOOD 49 - KWONEESUM RESERVOIR AND DAM – WEST TRIB. GRADING
- 50 KWONEESUM RESERVOIR AND DAM WEST TRIB. GRADING
- 51 KWONEESUM DAM AND RESEVOIR TYPICAL LARGE WOOD
- 52 KWONEESUM RESERVOIR AND DAM SPILLWAY PLAN AND PROFILE 53 - KWONEESUM RESERVOIR AND DAM - SPILLWAY CROSS-SECTIONS 54 - KWONFESUM RESERVOIR AND DAM - TRIBUTARY PLAN VIEW 55 - KWONEESUM RESERVOIR AND DAM - TRIBUTARY CROSS-SECTIONS 56 - KWONEESUM RESERVOIR AND DAM - DAM CONSTRUCTION SPOILS
- 60 WILDBOY CREEK PLAN AND PROFILE STA. 0+00 TO 5+00
- 61 WILDBOY CREEK PLAN AND PROFILE STA, 5+00 TO 10+00
- 68 WILDBOY CREEK TYPICAL LARGE WOOD CROSS-SECTIONS

- 69 WILDBOY CREEK TYPICAL LARGE WOOD CROSS-SECTION 70 - WILDBOY CREEK - TYPICAL LARGE WOOD CROSS-SECTIONS 71 - WILDBOY CREEK - TYPICAL LARGE WOOD CROSS-SECTIONS 72 - TYPICAL DETAILS
- 73 TYPICAL DETAILS
- 74 TYPICAL DETAILS
- 75 TYPICAL DETAILS
- 76 TYPICAL DETAILS
- 78 TYPICAL DETAILS
- 79 KWONEESUM RESERVOIR AND WILDBOY CREEK REVEGETATION PLAN
- 80 TYPICAL DETAILS REVEGETATION PLAN



#### **GENERAL NOTES**

#### THE CONTRACTOR SHALL ATTEND A MANDATORY PRE-BID SITE CONSTRUCTION ACCESS MEETING.

THE CONTRACTOR SHALL ATTEND A PRE-CONSTRUCTION THE CONTRACTOR SHALL ATTEND AT THE CONSTRUCTION OF THE CONTRACTOR SHALL ATTEND AT THE CONSTRUCT OF THE

ALL WORK SHALL CONFORM TO THE CURRENT EDITIONS OF STANDARD PLANS AND SPECIFICATIONS OF THE WASHINGTON STATE DEPARTMENT OF TRANSPORTATION (WSDOT), AND LOCAL STANDARDS UNLESS INDICATED OTHERWISE BY THE CONTRACT DOCUMENTS. IN CASE OF A CONFLICT BETWEEN THE REGULATORY STANDARDS OR SPECIFICATIONS, THE MORE STRINGENT WILL PREVAIL

#### WDFW IN-WATER WORK PERIODS

IN-WATER WORK SHALL OCCUR DURING THE PERMITTED IN-WATER WORK PERIOD STATED IN THE HYDRAULIC PROJECT APPROVAL

#### **EXISTING DATA**

TOPOGRAPHIC DATA COLLECTED BY ERS, INC USING RTK, TOTAL CONTROL FACILITIES TO COMPLY WITH APPLICABLE EROSION STATION, HYDROLITE AND DRONE BASED SFM FROM OCTOBER TO NOVEMBER 2018; GIS DATA PROVIDED BY VARIOUS AGENCIES INCLUDING AERIAL PHOTOGRAPHY, LIDAR, FISH USE, SURFACE SOILS INFORMATION, LAND OWNERSHIP, AND TRANSPORTATION ROUTES.

EXISTING DAM INFORMATION INCLUDED IN DEPARTMENT OF ECOLOGY DAM SAFETY REPORT (2006) INCLUDED SCANS OF DESIGN PLANS AND CH2M HILL SKETCH OF PRE-DAM TOPOGRAPHY.

HORIZONTAL DATUM: NAD83 WASHINGTON STATE PLANES, SOUTH ZONE, US FOOT VERTICAL DATUM: NAVD88

HISTORICAL PHOTOS PROVIDED AS SUPPLEMENTAL INFORMATION. SEE GEODESIGN REPORT PROVIDED AS SUPPLEMENTAL INFORMATION

#### SOILS

RESERVOIR SOILS WERE HIGHLY DISTURBED DURING DAM CONSTRUCTION, SEE HISTORICAL PHOTOS PROVIDED AS SUPPLEMENTAL INFORMATION. SEE GEODESIGN REPORT PROVIDED AS SUPPLEMENTAL INFORMATION.

SUBSURFACE SOILS ARE EXPECTED TO BE SILT, CLAY, SAND AND ANY EXCESS MATERIAL SHALL BE STOCKPILED NEATLY IN AN GRAVEL CONTRACTOR SHALL CONDUCT OWN INVESTIGATIONS IF ADDITIONAL DATA IS REQUIRED AT NO ADDITIONAL COST.

NON-SOIL DEBRIS MAY BE PRESENT IN EXCAVATION AREAS.

#### UTILITIES

UTILITIES LOCATED PRIOR TO CONSTRUCTION ACTIVITIES.

THE CONTRACTOR SHALL CALL (800-424-5555) FOR UTILITY LOCATE PRIOR TO CONSTRUCTION.

THE CONTRACTOR SHALL IMMEDIATELY CONTACT THE AFFECTED UTILITY SERVICE TO REPORT ANY DAMAGED OR DESTROYED UTILITIES.

THE CONTRACTOR SHALL PROVIDE EQUIPMENT OR LABOR TO RESTORATION CONSTRUCTION. TREES WILL BE FLAGGED AID THE AFFECTED UTILITY SERVICE IN REPAIRING DAMAGED OR FOLLOWING STAKING AND PRIOR TO CONSTRUCTION. DESTROYED UTILITIES AT NO ADDITIONAL COST.

ALL SAPLINGS AND TREES TO BE TRANSPLANTED OR REMOVED ALL TREES NOT MARKED FOR REMOVAL SHALL BE LEFT AND OWNER'S REPRESENTATIVE.

WITHIN THE LIMITS OF DISTURBANCE.

THE CONTRACTOR SHALL KEEP THE WORK AREAS IN NEAT CONDITION. FREE OF DEBRIS AND LITTER FOR THE DURATION OF THE PROJECT.

ALL DISTURBED AREAS INCLUDING ROADS, DRIVEWAYS AND ACCESS ROUTES SHALL BE RESTORED TO ORIGINAL CONDITION OR BETTER AND RE-VEGETATED PER PLANS.

ALL DISTURBED AREAS OUTSIDE THE LIMITS OF DISTURBANCE SHALL BE RESTORED TO ORIGINAL CONDITION OR BETTER AT NO ADDITIONAL COST

#### **EROSION CONTROL**

CONTRACTOR SHALL BE SOLELY RESPONSIBLE AT OWN EXPENSE FOR PROVIDING AND MAINTAINING ALL NECESSARY EROSION CONTROL REGULATIONS AND TO MAINTAIN CLEAN ACCESS ROUTES.

#### CONSTRUCTION STAKING

OWNER'S REPRESENTATIVE WILL PROVIDE STAKING, GRADE STAKES, AND ELEVATION CONTROL POINTS. SOME FIELD ADJUSTMENTS TO THE LINES AND GRADES ARE TO BE EXPECTED.

THE CONTRACTOR SHALL REPLACE DAMAGED OR DESTROYED CONSTRUCTION STAKES AT NO ADDITIONAL COST.

#### CONSTRUCTION MATERIALS

CONTRACTOR SHALL ALLOW FOR EXPANSION OF EXCAVATED MATERIAL AND COMPACTION OF PLACED MATERIAL AT NO ADDITIONAL MEASURE OR COST. MEASUREMENT AND PAYMENT SHALL NOT BE BASED ON WEIGHT TICKETS OR TRUCK MEASURE WITHOUT PRIOR WRITTEN APPROVAL

LOCATION, ALIGNMENT, AND ELEVATION ARE SUBJECT TO ADJUSTMENT BASED ON FIELD CONDITIONS, ENCOUNTERED BEDROCK, AND MATERIAL SIZE.

APPROVED LOCATION OF THE STOCKPILE AND STAGING AREA. CONCRETE FROM DAM DEMOLITION SHALL BE BURIED IN THE EXISTING SPILLWAY AREA AND COVERED WITH NATIVE SOILS.

#### TREE SALVAGE

REMOVED VEGETATION, INCLUDING TREES UP TO 12" DBH THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR HAVING SHALL BE INCORPORATED INTO LARGE WOOD STRUCTURES AS SLASH AT NO ADDITIONAL COST, VEGETATION LARGER THAN 12" DIAMETER AND 30' LENGTH SHALL BE USED AS STRUCTURAL ELEMENTS. SMALLER MATERIAL SHALL BE USED AS SLASH.

> SELECT SALVAGED, SMALL TREES REMOVED WITHIN CLEARING LIMITS SHALL BE REMOVED WHOLE WITH ROOT WAD AND USED IN RESTORATION CONSTRUCTION. SELECT, LARGE SALVAGED TREES ARE LISTED IN THE FELLED LOG LIST AND SHALL BE REMOVED WHOLE WITH ROOT WAD AND USED IN

DEBARK OR DAMAGE LIVE TREES.

KEEP OUT OF DRIP LINE OF EXISTING TREES TO REMAIN.

#### CONTRACTOR

THE CONTRACTOR SHALL SUBMIT THE FOLLOWING PLANS. INCLUDING THEIR MEANS AND METHODS OF PERFORMANCE FOR THEIR TESC PLAN OWNERS REVIEW AND APPROVAL:

- 1 SURFACE WATER DIVERSION PLAN FROM TRIBUTARIES AND AROUND RESERVOIR, INCLUDING PUMPING. REMOVAL OF ALL EQUIPMENT AND PIPING FOLLOWING SURFACE WATER DIVERSIONS.
- INITIAL DRAW DOWN PLAN, INCLUDING SILT TURBIDITY 2. CURTAIN, FLOATING INTAKES, SECURING AND MOVING SILT TURBIDITY CURTAIN AND FLOATING INTAKES. PIPING. PUMPING, SPRAYERS AND SPRAYER PLATFORMS.
- 3. FISH SALVAGE AND EXCLUSION PLAN. REMOVAL OF ALL EQUIPMENT AND PIPING FOLLOWING INITIAL DRAWDOWN
- STORM WATER POLLUTION PROTECTION PLAN (SWPPP) Δ
- EVAPORATIVE DEWATERING, INCLUDING SUMP PUMPS, 5. SUMP PUMP POWER SUPPLIES, HIGH HEAD PUMP. PIPING, PUMPING, SPRAYERS AND SPRAYER PLATFORMS. REMOVAL OF ALL EQUIPMENT AND PIPING FOLLOWING EVAPORATIVE DEWATERING.
- DAM MATERIAL HANDLING AND DISPOSAL. 6
- 7. VEGETATION ESTABLISHMENT PLAN.

#### **BID QUANTITIES**

| Bid Item                                 | Units | Quantity |
|--|-------|----------|
| MOBILIZATION                             | LS    | 1        |
| TESC, SPCC PLAN AND IMPLEMENTATION       | ى     | 1        |
| SURFACE WATER DIVERSION                  | LS    | 1        |
| INITIAL DRAWDOWN                         | 15    | 1        |
| EVAPORATIVE DEWATERING                   | LS    | 1        |
| CLEARING AND GRUBBING                    | AC    | 7        |
| REMOVAL OF DAM AND SPILLWAY              | ى     | 1        |
| COMMON BORROW INCLUDING HAUL             | CY    | 10260    |
| SELECT BORROW INCLUDING HAUL             | CY    | 9840     |
| GRAVEL BORROW INCLUDING HAUL             | CY    | 3000     |
| EMBANKMENT COMPACTION                    | CY    | 13000    |
| CHANNEL EXCAVATION AND HAUL              | CY    | 1000     |
| UNSUITABLE FOUNDATION EXCAVATION INCL. H | LS    | 1        |
| SMALL SALVAGED TREES                     | EA    | 50       |
| LARGE SALVAGED TREES                     | EA    | 55       |
| IMPORTED LOGS                            | EA    | 550      |
| GRAVEL BASE, METHOD C COMPACTION         | CY    | 70       |
| SEEDING                                  | AC    | 17       |
| RED-OSIER DOGWOOD, CUTTING               | EA    | 1500     |
| SITKA WILLOW, CUTTING                    | EA    | 1500     |
| SCOULER'S WILLOW, CUTTING                | EA    | 1500     |
| SALMONBERRY, 1-GALLON CONTAINER          | EA    | 1000     |
| RED ALDER, 1-GALLON CONTAINER            | EA    | 1000     |
| BIG LEAF MAPLE, 1 GALLON CONTAINER       | EA    | 1000     |
| MERTEN'S SEDGE, PLUG                     | EA    | 1000     |
| SMALLWING SEDGE, PLUG                    | EA    | 1000     |
| DAGGERLEAF RUSH, PLUG                    | EA    | 1000     |
| DOUGLAS FIR, 1-GALLON CONTAINER          | EA    | 1500     |
| WESTERN RED CEDAR, 1-GALLON CONTAINER    | EA    | 1500     |
| THIMBLEBERRY, 1-GALLON CONTAINER         | EA    | 1000     |
| SALAL, 1-GALLON CONTAINER                | EA    | 1000     |
| WESTERN SWORDFERN, 1 GALLON CONTAINER    | EA    | 1000     |
| WESTERN BRACKENFERN, 1-GALLON CONTAINER  | EA    | 1000     |
| DIVERSION OVERTOPPPING ALLOWANCE         | EA    | 2        |

#### FISH SALVAGE AND EXCLUSION PLAN

FISH SALVAGE WILL INCLUDE ASSISTANCE FROM WDFW AND COWLITZ TRIBE STAFF.

SHALL BE CLEARLY MARKED AND APPROVED BY THE OWNER STANDING UNDISTURBED. CONSTRUCTION ACTIVITY SHALL NOT THE CONTRACTOR SHALL PLAN OPERATIONS TO ANTICIPATE AND ALLOW FOR FISH EXCLUSION

WHEN PUMPING IS REQUIRED, THE CONTRACTOR SHALL INSTALL ISOLATE THE WORK AREA(S) WHEN FISH ARE PRESENT, AND PROVIDE A PUMP INTAKE FISH SCREEN THAT MEETS NMFS'S FISH SCREEN CRITERIA (NMFS 2011, OR MOST CURRENT). WIDER MESH SCREENS MAY BE USED AFTER ALL FISH HAVE BEEN REMOVED FROM THE ISOLATED AREA. WORK AREA ISOLATION AND FISH CAPTURE ACTIVITIES SHALL TAKE PLACE DURING PERIODS OF THE COOLEST AIR AND WATER TEMPERATURES POSSIBLE, NORMALLY FARLY IN THE MORNING VERSUS LATE IN THE DAY, AND DURING CONDITIONS APPROPRIATE TO MINIMIZE STRESS TO FISH SPECIES PRESENT.

#### TRIBUTARY DIVERSIONS

DURING INITIAL DRAW DOWN OF THE RESERVOIR AND PUMPING OF DIVERTED FLOWS, TRIBUTARY INTAKES MUST BE SCREENED. THE CONTRACTOR SHALL SCREEN TRIBUTARY DIVERSION INLETS WITH SEINE NETS. THE CONTRACTOR SHALL CLEAR FISH UPSTREAM OF THE DIVERSION N DAM USING SEINE NETS AND SCARE RESPONSE. THIS CLEARING PROCESS WILL PROCEED TO A LOCATION WHERE ONE SIDE OF THE SEINE NET CAN BE SEALED AND SECURED TO THE TRIBUTARY STREAM BANK. AFTER ONE SIDE OF THE SEINE NET IS SECURED AND SEALED, THE OTHER END OF THE SEINE NET WILL BE ADVANCED UPSTREAM TO APPROXIMATELY 45 DEGREES TO FLOW. THE SEINE NET SHALL THEN BE SEALED TO THE STREAMBED USING A CONTINUOUS LINE OF SANDBAGS AND THE UPSTREAM SIDE OF THE SEINE NET SHALL BE SEALED TO THE OPPOSITE BANK.

THE CONTRACTOR SHALL CONTINUALLY MONITOR THE SEINE NETS AND CLEAR DEBRIS FROM THE SEINE NETS AS NECESSARY

ALL FISH TRAPPED IN RESIDUAL POOLS WITHIN THE PROJECT AREA WILL BE CAREFULLY COLLECTED BY SEINE AND/OR DIP NETS AND PLACED IN CLEAN TRANSFER CONTAINERS WITH ADEQUATE VOLUME OF FRESH RIVER WATER.

CAPTURED FISH SHALL BE IMMEDIATELY RELEASED INTO RIVER AT AREAS SELECTED BY A COWLITZ TRIBE BIOLOGIST.

FISH SHALL BE EXCLUDED FROM THE WORK AREA WITH SEINE NET OR OTHER METHOD APPROVED BY WDFW AND COWLITZ TRIBE PERSONNEL.

#### LARGE SALVAGED TREE LIST

| Salvaged | Approx. DBH | Nates    | Large Wood   | Sa |
|----------|-------------|----------|--------------|----|
| Tree #   | (Inches)    | NOLES    | Structure ID |    |
| 1        | 20          | Downed   | A            |    |
| 2        | 24          | Standing | A            |    |
| 3        | 24          | Standing | В            |    |
| 4        | 24          | Standing | В            |    |
| 5        | 24          | Standing | С            |    |
| 6        | 24          | Standing | С            |    |
| 7        | 20          | Standing | D            |    |
| 8        | 24          | Standing | D            |    |
| 9        | 28          | Standing | E            |    |
| 10       | 26          | Standing | E            |    |
| 11       | 30          | Standing | F            |    |
| 12       | 30          | Standing | F            |    |
| 13       | 30          | Standing | G            |    |
| 14       | 24          | Standing | G            |    |
| 15       | 24          | Standing | н            |    |
| 16       | 30          | Standing |              |    |
| 17       | 22          | Standing | J            |    |
| 18       | 36          | Standing | к            |    |
| 19       | 32          | Standing | к            |    |
| 20       | 36          | Standing | L            |    |
| 21       | 26          | Standing | М            |    |
| 22       | 34          | Standing | N            |    |
| 23       | 34          | Standing | N            |    |
| 24       | 28          | Standing | 0            |    |
| 25       | 26          | Standing | 0            |    |

### LIVE TREES

#### alvaged Approx. DBH Large Wood Notes Tree # (Inches) Structure If 26 26 Standing P 27 26 Standing 8 28 36 Standing P 29 36 Standing 30 34 Standing 31 30 Standing 32 36 Standing 33 36 Standing 8 34 36 Standing 24 Standing 35 30 Standing 1 36 37 30 Standing \ 38 36 Standing |W 39 30 Standing X 40 30 Standing Y 41 30 Standing 42 30 Downed 30 Standing 2 43 30 Standing AA 44 45 30 Standing AB 46 36 Standing AC 47 40 Standing AC

### RESERVOIR

FISH SALVAGE IN THE RESERVOIR SHALL OCCUR AFTER THE INITIAL DRAW DOWN OF THE RESERVOIR TO CONCENTRATE FISH IN A REDUCED AREA.

WDFW WILL ASSIST WITH THEIR ELECTRO-FISHING BOAT.THE CONTRACTOR SHALL REMOVE SOFT SOILS IN THE DRAW DOWN RESERVOIR AND ASSIST WDFW STAFF IN LAUNCHING AND TRAILORING ELECTRO-FISHING BOAT. ELECTRO-FISHING WILL CONTINUE UNTIL AS LONG AS A REASONABLE EFFORT YIELDS REASONABLE RESULTS.

#### WILDBOY CREEK

THE CONTRACTOR SHALL PERFORM FISH EXCLUSION IN WILDBOY CREEK WITH ASSISTANCE FROM THE COWLITZ INDIAN TRIBE FISHERIES BIOLOGIST, FISH, SALVAGE SHALL INCLUDE THE CONTRACTOR PROVIDING SCREENED INTAKE PUMPS AND OPERATING THE PUMPS TO CONCENTRATE FISH IN POOLS. THE POOLS SHALL BE PUMPED DOWN TO ALLOW FOR SYSTEMATIC SEINE NETTING THROUGH THE WORK AREAS. FOLLOWING SEINE NETTING, THE WORK AREAS WILL BE ISOLATED TO EXCLUDE FISH WITH SEINE NETS THAT MUST BE KEPT CLEAN OF DEBRIS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR SKIMMING DEBRIS OFF SEINE NETS THROUGHOUT CONSTRUCTION. ANY SEINE NETS DAMAGED BY THE CONTRACTOR SHALL BE REPLACED AT THE CONTRACTOR'S FXPFNSF.



#### EROSION/SEDIMENTATION CONTROL (ESC) PLAN

THE EROSION AND SEDIMENT CONTROL (ESC) PLAN PROVIDED IS FOR INFORMATIONAL PURPOSES ONLY. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR PROVIDING EROSION CONTROL MEASURES TO COMPLY WITH APPLICABLE REGULATIONS

THE RECOMMENDATIONS FOR AN ESC PLAN INCLUDED HEREIN WILL PROVIDE A GUIDELINE FOR THE CONTRACTOR TO DEVELOP AND IMPLEMENT AN ESC PLAN.

- A. THE IMPLEMENTATION OF AN ESC PLAN AND THE CONSTRUCTION, MAINTENANCE, REPLACEMENT, AND UPGRADING OF THESE ESC FACILITIES IS THE RESPONSIBILITY OF THE CONTRACTOR UNTIL ALL CONSTRUCTION IS COMPLETED AND APPROVED AND VEGETATION/LANDSCAPING IS ESTABLISHED.
- B. THE BOUNDARIES OF THE CLEARING LIMITS SHOWN ON THIS PLAN SHALL BE CLEARLY FLAGGED IN THE FIELD PRIOR TO CONSTRUCTION. DURING THE CONSTRUCTION PERIOD, NO DISTURBANCE BEYOND THE FLAGGED CLEARING LIMITS SHALL BE PERMITTED. THE FLAGGING SHALL BE MAINTAINED BY THE CONTRACTOR FOR THE DURATION OF CONSTRUCTION.
- C. ESC FACILITIES AS APPROXIMATELY SHOWN ON THIS PLAN ARE TO BE CONSTRUCTED PRIOR TO CLEARING AND GRADING ACTIVITIES, AND IN SUCH A MANNER AS TO ENSURE THAT SEDIMENT AND SEDIMENT-LADEN WATER DO NOT ENTER SURFACE WATERS, THE DRAINAGE SYSTEM, OR VIOLATE APPLICABLE WATER STANDARDS
- D. THE ESC FACILITIES SHOWN ON THIS PLAN ARE THE MINIMUM REQUIREMENTS FOR ANTICIPATED SITE CONDITIONS. DURING THE CONSTRUCTION PERIOD, THESE ESC FACILITIES SHALL BE UPGRADED AS NEEDED AT NO ADDITIONAL COST FOR UNEXPECTED STORM EVENTS AND TO ENSURE THAT SEDIMENT AND SEDIMENT-LADEN WATER DO NOT LEAVE THE SITE.
- THE ESC FACILITIES SHALL BE INSPECTED DAILY BY THE CONTRACTOR AND MAINTAINED AS NECESSARY TO ENSURE THEIR CONTINUED FUNCTIONING.
- F. THE ESC FACILITIES ON INACTIVE SITES SHALL BE INSPECTED AND MAINTAINED A MINIMUM OF ONCE A MONTH OR WITHIN THE 24 HOURS FOLLOWING A STORM FVFNT
- G. STABILIZED CONSTRUCTION ENTRANCES AND ADDITIONAL MEASURES MAY BE REQUIRED AND SHALL BE MAINTAINED FOR THE DURATION OF THE PROJECT TO ENSURE ALL ACCESS ROADS ARE KEPT CLEAN AT NO ADDITIONAL COST

### INSPECTION AND MAINTENANCE

ALL ESC FACILITIES SHALL BE INSPECTED, MAINTAINED, AND REPAIRED AS NEEDED TO ASSURE CONTINUED PERFORMANCE OF THEIR INTENDED FUNCTION. ALL ESC FACILITIES SHALL BE INSPECTED DAILY AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5 INCHES OF RAIN PER 24 HOUR PERIOD AND AFTER EVENTS EXCEEDING 2 HOURS DURATION.

#### CONTRACTOR'S ESC RECORD

WEEKLY REPORTS SUMMARIZING THE SCOPE OF INSPECTIONS, THE PERSONNEL CONDUCTING THE INSPECTION, THE DATE(S) OF THE INSPECTION, MAJOR OBSERVATIONS RELATING TO THE IMPLEMENTATION OF THE CONTRACTOR'S EROSION AND SEDIMENT CONTROL PLAN, AND ACTIONS TAKEN AS A RESULT OF THESE INSPECTIONS SHALL BE PREPARED AND RETAINED ON SITE BY THE CONTRACTOR. IN ADDITION, A RECORD OF THE FOLLOWING DATES SHALL BE INCLUDED IN THE REPORTS:

1. WHEN MAJOR GRADING ACTIVITIES OCCUR.

- 2. DATES OF RAINFALL EVENTS EITHER EXCEEDING 2 HOURS DURATION OR MORE THAN 0.5 INCHES/24 HOURS.
- 3. WHEN CONSTRUCTION ACTIVITIES TEMPORARILY OR PERMANENTLY CEASE ON SITE, OR ON A PORTION OF THE SITE.
- 4. WHEN STABILIZATION MEASURES ARE INITIATED FOR PORTIONS OF THE SITE.
- 5. ESC RECORDS SHALL BE MADE AVAILABLE TO THE OWNER AND OWNER'S REPRESENTATIVE ON REQUEST AND SHALL BE PROVIDED FOR REVIEW AND APPROVAL PRIOR TO APPLICATION FOR PAYMENT.

#### STABILIZE SOILS AND PROTECT SLOPES

FROM MAY 1 THROUGH SEPTEMBER 30. ALL EXPOSED SOILS SHALL BE PROTECTED FROM EROSION BY MULCHING, HYDROSEED COVERING, OR OTHER APPROVED MEASURES WITHIN THREE DAYS OF GRADING. FROM OCTOBER 1 THROUGH APRIL 30, ALL EXPOSED SOILS MUST BE PROTECTED WITHIN 2 DAYS OF GRADING. SOILS SHALL BE STABILIZED BEFORE A WORK SHUTDOWN, HOLIDAY OR WEEKEND IF NEEDED BASED ON THE WEATHER FORECAST. SOIL STOCK PILINGS MUST BE STABILIZED AND PROTECTED WITH SEDIMENT TRAPPING MEASURES. MULCH AS SOON AS PRACTICAL ALL DISTURBED AREAS NOT INDICATED IN THE CONTRACT DOCUMENTS FOR OTHER PERMANENT STABILIZATION. MEASURES. HAY, STRAW, AND MULCH USED ON SITE SHALL BE 99.9% WEED FREE.

DESIGN, CONSTRUCT, AND PHASE CUT AND FILL SLOPES IN A MANNER THAT WILL MINIMIZE EROSION. REDUCE SLOPE VELOCITIES ON DISTURBED SLOPES BY PROVIDING TEMPORARY BARRIERS. STORMWATER FROM OFF SITE SHOULD BE HANDLED SEPARATELY FROM STORMWATER GENERATED ON SITE.

#### AFTER FINAL SITE STABILIZATION

ALL TEMPORARY EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER FINAL SITE STABILIZATION IS ACHIEVED OR AFTER THE TEMPORARY BEST MANAGEMENT PRACTICES (BMPS) ARE NO LONGER NEEDED. TRAPPED SEDIMENT SHALL BE REMOVED FROM THE SITE OR INCORPORATED INTO FINISHED GRADING. DISTURBED SOIL AREAS RESULTING FROM REMOVAL SHALL BE PERMANENTLY STABILIZED.

### CONSTRUCTION DEWATERING

CONTRACTOR SHALL PERFORM CONSTRUCTION DEWATERING IN SUCH A MANNER AS TO AVOID THE RELEASE OF SEDIMENT-LADEN WATER TO SURFACE WATERS. SEDIMENT LADEN WATER MAY BE PUMPED TO AN UPLAND DISCHARGE LOCATION AND ALLOWED TO INFILTRATE INTO THE GROUND. IF SURFACE RUNNOFF IS OCCURING AS A RESULT OF DEWATERING OPERATIONS, THE CONTRACTOR MAY BE REQUIRED TO THROTTLE DOWN PUMPS AS NECESSARY TO COMPLY WITH LAWS AND PERMIT REQUIREMENTS AT NO ADDITIONAL COST TO THE OWNER

#### SPECIAL PROVISIONS

#### INTRODUCTION

THE WASHINGTON STATE DEPARTMENT OF TRANSPORTATION'S STANDARD SPECIFICATIONS FOR ROAD. BRIDGE AND MUNICIPAL CONSTRUCTION 2020 (WSDOT STANDARD SPECIFICATIONS) SHALL APPLY UNLESS OTHERWISE NOTED IN THE FOLLOWING SPECIAL PROVISIONS. THE "CONTRACTING AGENCY" OR "OWNER" SHALL BE THE COWLITZ INDIAN TRIBE. ADDITIONAL SPECIFICATIONS IN THE FOLLOWING CONTRACT SECTIONS ARE INCLUDED FOR ITEMS NOT COVERED BY THE WSDOT STANDARD SPECIFICATIONS.

SECTIONS 1-02, 1-03, AND 1-08 (EXCEPT 1-08.6, 1-08.7, 1-08.8) OF THE STANDARD SPECIFICATIONS DO NOT APPLY.

### ITEM 001- TESC, SPCC PLAN AND IMPLEMENTATION

### DESCRIPTION

THIS WORK SHALL PROVIDE FOR PREPARATION, IMPLEMENTATION, AND REMOVAL OF A TEMPORARY EROSION SEDIMENT CONTROL (TESC) PLAN AND FOR THE PREPARATION AND IMPLEMENTATION OF A SPILL PREVENTION CONTROL AND COUNTERMEASURE (SPCC) PLAN IN ACCORDANCE WITH SECTION 1-07.15 OF THE STANDARD SPECIFICATIONS, AND AS AMENDED BY THESE SPECIAL PROVISIONS.

1. THE CONTRACTOR SHALL SUBMIT A TESC FOR THE PROJECT TO THE OWNER FOR APPROVAL. THE TESC MUST SATISFY THE REQUIREMENTS OF THE WASHINGTON DEPARTMENT OF ECOLOGY NPDES STORMWATER GENERAL PERMIT FOR CONSTRUCTION ACTIVITY AND ALL OTHER APPLICABLE PERMITS. THE TESC INCLUDED IN THE DRAWINGS AND DESCRIBED HEREIN IS INTENDED TO PROVIDE A BASELINE FOR SEDIMENT AND EROSION CONTROL AND DOES NOT ENSURE THAT PAYMENT FOR MOBILIZATION SHALL BE BY THE LUMP SUM CONTRACT PRICE FOR, THE STANDARDS ESTABLISHED BY ANY APPLICABLE PERMITS WILL BE MET. THE 'MOBILIZATION', PARTIAL PAYMENTS WILL BE MADE AS IN ACCORDANCE WITH CONTRACTOR MAY USE THESE MEASURES OR ALTERNATIVE MEASURES OF HIS OWN DESIGN TO ENSURE SATISFACTORY PERFORMANCE AND THAT THE FROSION SECTION 1-09.9 OF THE STANDARD SPECIFICATIONS. PAYMENT SHALL BE CONTROL REQUIREMENTS OF ALL APPLICABLE PERMITS ARE MET. THE CONSIDERED FULL COMPENSATION FOR ALL EQUIPMENT, LABOR, TOOLS, CONTRACTOR SHALL BE NAMED AS THE PERMIT HOLDER. THE CONTRACTOR MATERIALS, AND INCIDENTALS NECESSARY TO COMPLETE THIS WORK AS SPECIFIED. SHALL BE RESPONSIBLE FOR IMPLEMENTING, INSPECTING AND FILING REPORTS. MAINTAINING, REPLACING, AND REMOVING TESC AND SPCC MEASURES. THE ITEM 003 - CLEARING AND GRUBBING PLAN SHALL INCLUDE THE NAME, ADDRESS AND 24-HOUR CONTACT NUMBER OF THE PERSON RESPONSIBLE FOR EROSION PREVENTION AND SEDIMENT CONTROL DESCRIPTION MEASURES. ELEMENTS OF THE TESC PLAN HAVE BEEN BROKEN OUT FOR MEASUREMENT AND PAYMENT AS DESCRIBED BELOW.

- 2. THE CONTRACTOR SHALL INCLUDE THE FOLLOWING IN THE TESC PLAN:
- a. SURFACE WATER DIVESION PLAN FROM TRIBUTARIES AND RESERVOIR. INCLUDING PUMPING, AND GRAVITY FLOW. REMOVAL OF ALL EQUIPMENT AND PIPING FOLLOWING SURFACE WATER DIVERSIONS.
- b. INITIAL DRAWDOWN PLAN. INCLUDING SILT TURBIDITY CURTAIN. FLOATING INTAKES, SECURING AND MOVING SILT TURBIDITY CURTAIN AND FLOATING INTAKES, PIPING, PUMPING, SPRAYERS AND SPRAYER PLATFORMS
- c. FISH SALVAGE AND EXCLUSION PLAN. REMOVAL OF ALL EQUIPMENT AND PIPING.
- d. STORM WATER POLLUTION PROTECTION PLAN (SWPPP)
- e. EVAPORATIVE DEWATERING, INCLUDING SUMP PUMPS, SUMP PUMP POWER SUPPLIES, HIGH HEAD PUMPS, PIPING, PUMPING, SPRAYERS AND SPRAYER PLATFORMS INCLUDING GRANULAR FILL. REMOVAL OF ALL EQUIPMENT AND PIPING FOLLOWING EVAPORATIVE DEWATERING.
- f. DAM MATERIAL HANDLING AND DISPOSAL PLAN.
- g. VEGETATION ESTABLISHMENT PLAN
- 3. A SPILL CONTAINMENT KIT SHALL BE ON SITE AND CREWS SHALL BE TRAINED IN ITS USE
- 4. BIODEGRADABLE HYDRAULIC FLUID SHALL BE INSTALLED INTO EACH PIECE OF HEAVY MACHINERY WORKING WITHIN 50 FEET OF THE RIVER.

### MEASUREMENT

"TESC, SPCC PLAN AND IMPLEMENTATION," INCLUDING FISH RESCUE AND EXCLUSION, WILL BE MEASURED BY LUMP SUM. "SURFACE WATER DIVERSION", HDPE PIPING, DIVERSION DAMS, TEMPORARY PUMPING, GRAVITY DIVERSION AND REMOVAL OF HDPE PIPING WILL BE MEASURED BY LUMP SUM. "INITIAL DRAWDOWN", INCLUDING SILT TURBIDITY CURTAIN, FLOATING INTAKES, HDPE PIPING TO AND FROM PUMPS, HIGH-HEAD PUMPS, SPRAYERS AND SPRAYER PLATFORMS AND REMOVAL OF ALL EQUIPMENT AND PIPING WILL BE MEASURED BY LUMP SUM. "EVAPORATIVE DEWATERING", INCLUDING SUMP PUMPS AND THEIR POWER SUPPLIES, HDPE PIPING TO AND FROM PUMPS, HIGH-HEAD PUMPS, SPRAYERS AND SPRAYER PLATFORMS AND REMOVAL OF ALL EQUIPMENT AND PIPING PLATFORMS WILL BE MEASURED BY LUMP SUM.

### PAYMENT

PAYMENT SHALL BE CONSIDERED FULL COMPENSATION FOR ALL EQUIPMENT, LABOR, TOOLS, MATERIALS, AND INCIDENTALS NECESSARY TO COMPLETE THIS WORK AS SPECIFIED. PAYMENT WILL BE MADE IN ACCORDANCE WITH SECTION 1-04.1 FOR THE FOLLOWING BID ITEMS: "TESC, SPCC PLAN AND IMPLEMENTATION", "SURFACE WATER DIVERSION", "INITIAL DRAWDOWN", AND "EVAPORATIVE DEWATERING" PER LUMP SUM.

### **ITEM 002 - MOBILIZATION**

THIS ITEM SHALL CONSIST OF PREPARATION WORK AND OPERATIONS PERFORMED BY THE CONTRACTOR IN ACCORDANCE WITH THE PROVISIONS OF SECTION 1-09.7 OF THE WASHINGTON DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS (STANDARD SPECIFICATIONS). TEMPORARY SITE ACCESS SHALL BE ALONG ALIGNMENTS SHOWN IN THE PLANS. MINOR DEVIATIONS TO THE ALIGNMENTS MAY OCCUR AS DIRECTED BY THE OWNER TO PRESERVE SENSITIVE AREAS OR TREES, OR OTHER FEATURES IDENTIFIED IN THE FIELD. DEVIATIONS FROM THE ALIGNMENTS SHOWN IN THE PLANS SHALL BE APPROVED BY OWNER PRIOR TO USE. SITE ACCESS ROUTES SHALL BE MAINTAINED AND RESTORED TO ORIGINAL OR BETTER CONDITION.

#### MEASUREMENT AND PAYMENT

THIS ITEM CONSISTS OF CLEARING, AND GRUBBING, AND SALVAGING MATERIAL IN ACCORDANCE WITH SECTION 2-01 OF THE STANDARD SPECIFICATIONS, AND AS AMENDED BY THESE SPECIAL PROVISIONS.

- 1. GRUBBING IS NECESSARY AT ACCESS ROADS, STAGING AND STOCKPILE AREAS AND AT SPRAYER PLATFORM LOCATIONS, WHERE SHOWN ON THESE DRAWINGS.
- 2. CLEARING AND GRUBBING SHALL TIP OVER TREES TO BE REMOVED AND SALVAGED AS SLASH, SALVAGED SMALL TREES OR SALVAGED LARGE TREES. OPEN BURNING OF RESIDUE FROM LAND CLEARING IS NOT ALLOWED.
- 3. SLASH SHALL BE CONSIDERED ANY NATIVE VEGETATION WITH TRUNKS LESS THAN 10 INCHES DIAMETER

### MEASUREMENT

"CLEARING AND GRUBBING" WILL BE MEASURED PER ACRE.

### PAYMENT

"CLEARING AND GRUBBING", PER ACRE.

#### ABBREVIATIONS

| APPROX | APPROXIMATE                                |                      |                        |                     |            |               |
|--------|--|----------------------|------------------------|---------------------|------------|---------------|
| BMP    | BEST MANAGEMENT PRACTICES                  |                      |                        |                     |            |               |
| СМР    | CORRUGATED METAL PIPE                      |                      |                        |                     |            |               |
| CY     | CUBIC YARDS                                |                      | M                      | $P. \lambda $       | 4          |               |
| DIA    | DIAMETER                                   | <b>J</b>             | 1 LAIN                 | WASU                | <i>?</i> ¢ | 1             |
| DBH    | DIAMETER BREAST HEIGHT                     | Jŝ                   | Nov.                   |                     | X          |               |
| EA     | EACH                                       | 4                    | E I                    |                     | 3          |               |
| ELEV   | ELEVATION                                  |                      | 5 <b>4</b>             | SP2                 | Z          |               |
| FT     | FEET                                       |                      |                        | <b>K</b> <i>n</i>   |            |               |
| GIS    | GEOGRAPHICAL INFORMATION SYSTEM            |                      | PEC 3                  | 4576<br>1075 BED    |            |               |
| HORIZ  | HORIZONTAL                                 |                      | ESSION                 | STEN                | $31^{1}$   | <b>~</b>      |
| N      | INCHES                                     |                      | TON                    | AL D.               | ~          |               |
| NV     | INVERT                                     |                      |                        |                     |            |               |
| LCFEG  | LOWER COLUMBIA FISH<br>ENHANCEMENT         | 3 -                  |                        |                     | -          | -             |
|        | GROUP                                      | REV: DES             | CRIPTION:              |                     | BY:        | DATE:         |
| WM     | LARGE WOODY MATERIAL                       | STATUS: P            | RELIMIN                | VARY D              | ESI        | GN            |
| MAX    | MAXIMUM                                    |                      |                        |                     |            |               |
| MIN    | MINIMUM                                    |                      |                        |                     |            |               |
| NMFS   | NATIONAL MARINE FISHERIES<br>SERVICE       |                      | PΑ                     | <b>K</b> r          |            |               |
| OHW    | ORDINARY HIGH WATER                        | e                    | exce                   | lien                | ce         |               |
| %      | PERCENT                                    | 302 W.<br>Bingen, W. | Steuben St.<br>A 98605 | .#6<br>www          | v.ers4lif  | e.com         |
| RM     | RIVER MILE                                 |                      |                        |                     |            |               |
| RTK    | REAL TIME KINEMATICS                       |                      | COWLIT                 | Z INDIAN            | TRI        | 3E            |
| SFM    | STRUCTURE FROM MOTION                      |                      | VANCOUVE               | ER, WA, 98665       |            |               |
| STA    | STATION                                    | and a                | /                      |                     |            |               |
| TESC   | TEMPORARY EROSION AND<br>SEDIMENT CONTROL  | SITE:                | kwone<br>Remov         | ESUM DA<br>AL DESIG | M.<br>N    |               |
| TBD    | TO BE DETERMINED                           | TITLE:               |                        |                     |            |               |
| ТҮР    | TYPICAL                                    |                      |                        |                     |            |               |
| VERT   | VERTICAL                                   |                      | GENER                  | RAL NOTE            | S          |               |
| WDFW   | WASHINGTON DEPARTMENT OF FISH AND WILDLIFE | SCALE:               | DATE:                  | DRAWN:              | CHEC       | KED:          |
| WSE    | WATER SURFACE ELEVATION                    | PROJ. NO:            | 6/4/21                 | RP                  | Total      | BN<br>Sheets: |
| YR     | YEAR                                       | -                    |                        | 3                   | 8          | 30            |
|        |  |                      |                        |                     |            |               |

### **ITEM 004 - REMOVAL OF STRUCTURES AND** OBSTRUCTIONS

#### DESCRIPTION

THIS ITEM CONSISTS OF REMOVAL OF THE KWONEESUM DAM AND ITS APPURTENANCES, INCLUDING SPILLWAY.

- 1. DAM AND SPILLWAY REMOVAL WILL BE INCLUDED IN THE REQUIREMENTS OF SECTION 2.02 REMOVAL OF STRUCTURES AND OBSTRUCTIONS
- 2. DAM REMOVAL AS SHOWN ON THESE DRAWINGS.
- 3. REUSE OF EXISTING ROCK LOCATED IN THE DAM AND THE SPILLWAY FOR ROCK EMBANKMENT AND CHANNEL EXCAVATION.
- 4. REMOVE AND DISPOSE, OFF SITE, OF ALL DEMOLISHED REINFORCED CONCRETE MATERIALS.

#### MEASUREMENT

"REMOVAL OF DAM AND SPILLWAY" APPROXIMATELY 20.000 CY (IN PLACE) INCLUDING 6.000 CY (IN PLACE) OF REINFORCED CONCRETE WILL BE MEASURED BY LUMP SUM.

#### PAYMENT

"REMOVAL OF DAM AND SPILLWAY", LUMP SUM.

#### **ITEM 005 ROADWAY EXCAVATION AND** EMBANKMENT

#### DESCRIPTION

THIS ITEM CONSISTS OF EXCAVATING, LOADING, HAULING, PLACING, AND EMBANKMENT COMPACTING, OR OTHERWISE PLACEMENT OF THE MATERIAL IN ACCORDANCE WITH SECTION 2-03 OF THE STANDARD SPECIFICATIONS, AND AS AMENDED BY THESE SPECIAL PROVISIONS.

- 1. PORTIONS OF WORK WILL BE IN WATER. THE CONTRACTOR IS ADVISED THAT WATER WILL BE ENCOUNTERED THROUGHOUT EXCAVATION ARFA
- 2. THIS ITEM INCLUDES DETAIL GRADING TO SHAPE OF EXCAVATION AS SHOWN IN THESE DRAWINGS.
- 3. THE FOLLOWING PROVISION IN SECTION 2-03.3(3) "ROCK EXCAVATION - WHEN THE CONTRACTOR FINDS ROCK OR OTHER HARD MATERIAL AT THE SUBGRADE ELEVATION, IT SHALL BE EXCAVATED THE FULL WIDTH OF THE ROADBED TO AT LEAST 6 INCHES BELOW SUBGRADE. THEN BACKFILLED WITH ROCK FRAGMENTS, GRAVEL, OR OTHER FREE-DRAINING MATERIAL NOT MORE THAN 4 INCHES IN DIAMETER.' SHALL BE REMOVED.
- 4. ADD THE FOLLOWING PROVISIONS TO SECTION 2-03.3(14), "ACCESS ROADS IN THE FOOTPRINT OF THE EXISTING RESERVOIR SHALL BE CONSIDERED ROCK EMBANKMENTS. ALL OTHER FILL IN THE RESERVOIR SHALL BE CONSIDERED EARTH EMBANKMENT."
- 5. ADD THE FOLLOWING PROVISION TO SECTION 2-03.3(14)C, "EARTH EMBANKMENTS SHALL USE COMPACTION METHOD A.
- 5. ADD THE FOLLOWING PROVISION TO SECTION 2-03.3(14)E, "THE SLURRY LOCATED AT THE BOTTOM OF THE RESERVOIR SHALL BE CONSIDERED UNSUITABLE FOUNDATION EXCAVATION." THE FINE SOILS (SILTS AND CLAYS) LOCATED AT THE BOTTOM OF THE RESERVOIR SHALL BE INITIALLY DEWATERED THROUGH THE EVAPORATIVE DEWATERING PROCESS INDICATED ON THE DRAWINGS. THE FINE SOILS (SILTS AND CLAYS) SHALL BE FURTHER DEWATERED BY PLACING THEM WITHIN CONTAINMENT AREAS ALONG THE EDGE OF THE DRAINED RESERVOIR AND ALLOWING THEM TO DRAIN FOR A PERIOD OF TIME. THE DEWATERED FINE SOILS SHALL BE MIXED WITH COMMON BORROW MATERIALS AND THEN SPREAD WITHIN PROPOSED UPLAND AND RIPARIAN AREAS IN THE FORMER RESERVOIR FOOTPRINT TO PROVIDE A GROWING MEDIUM FOR NATIVE VEGETATION.
- ADD THE FOLLOWING PROVISION TO SECTION 2-03.3(14)J, "SALVAGE OF DELTAIC MATERIALS LOCATED WHERE TRIBUTARY CHANNELS ENTER THE EXISTING RESERVOIR SHALL BE CONSIDERED GRAVEL BORROW INCLUDING HAUL
- 8. ADD THE FOLLOWING PROVISION TO SECTION 2-03.3(14)K, "SALVAGE OF EARTH AND ROCK MATERIALS LOCATED IN THE DAM CONSTRUCTION SPOILS PILE SHALL BE CONSIDERED SELECT OR COMMON BORROW INCLUDING HAUL. THE SORTING, STOCKPILE, HAUL AND PLACEMENT OF STREAMBED COBBLES AND STREAMBED BOULDERS SHALL BE INCLUDED IN IN THE VOLUME OF SELECT AND COMMON BORROW. MATERIALS FROM THE ORIGINAL DAM CONSTRUCITON SPOILS PILE SHALL BE FURTHER SORTED IN 12-INCH

MINUS COBBLE, AS DEFINED IN 9.03.11(2) AND STREAMBED BOULDERS, AS DEFINED IN 9.03.11(3). PLACING FILL SOURCED FROM SELECT AND COMMON BORROW, INCLUDING COBBLE AND STREAMBED BOULDERS SHALL BE CONSIDERED INCIDENTAL TO "SELECT BORROW INCLUDING HAUL", "COMMON BORROW INCLUDING HAUL", AND "DAM AND SPILLWAY DEMOLITION".

9. REPLACE SECTION 2-03.3(14)M WITH THE FOLLOWING, "CHANNEL EXCAVATION WILL INCLUDE PLACEMENT OF COBBLES AND STREAMBED BOULDERS, GRAVEL BORROW INCLUDING HAUL AND SELECT BORROW INCLUDING HAUL, INCLUDING COBBLES AND SREAMBED BOULDERS, IN EXISTING AND PROPOSED CHANNELS. THESE MATERIALS SHALL BE SOURCED FROM DELTAIC DEPOSITS, THE DAM CONSTRUCTION SPOILS PILE AND DAM AND SPILLWAY DEMOLITION CHANNEL EXCAVATION SHALL BE CONSIDERED INCIDENTAL TO "SELECT BORROW INCLUDING HAUL", "COMMON BORROW INCLUDING HAUL", "GRAVEL BORROW INCLUDING HAUL", AND "DAM AND SPILLWAY DEMOLITION." CHANNEL EXCAVATION INCLUDING HAUL SHALL INCLUDE PROVIDING AND INSTALLING IMPORTED STREAMBED GRAVEL. IMPORTED STREAMBED GRAVEL SHALL CONSIST OF 50% BY WEIGHT STREAMBED SEDIMENT DEFINED IN 9-03.11(1) AND 50% (BY WEIGHT) 4" COBBLES DERINED IN 9-03.11(2)."

10. REPLACE THE FIRST PARAGRAPH IN SECTION 2-03.4. WITH THE FOLLOWING, "COMMON BORROW, SELECT BORROW AND GRAVEL BORROW ITEMS WILL BE MEASURED BY THE CUBIC YARD. COMMON BORROW, SELECT BORROW AND GRAVEL BORROW MATERIALS WILL BE MEASURED IN THE POSITION THEY OCCUPIED BEFORE THE EXCAVATION WAS PERFORMED. AN ORIGINAL GROUND MEASUREMENT WILL BE TAKEN USING CROSS-SECTION OR DIGITAL TERRAIN MODELING SURVEY TECHNIQUES. FOR ROADWAY EXCAVATION THE ORIGINAL GROUND WILL BE COMPARED WITH THE PLANNED FINISHED SECTION SHOWN IN THE PLANS. SLOPE/GROUND INTERCEPT POINTS DEFINING THE LIMITS OF THE MEASUREMENT WILL BE AS STAKED. CHANNEL EXCAVATION WILL ONLY INCLUDE ROCK FILLS PLACED IN EXISTING AND PROPOSED CHANNELS AND SHALL BE INCIDENTAL TO OBTAINING THEIR SOURCE MATERIALS FROM EITHER, "SELECT BORROW INCLUDING HAUL", "COMMON BORROW INCLUDING HAUL", "GRAVEL BORROW INCLUDING HAUL", OR "DAM AND SPILLWAY DEMOLITION.". FOR COMMON BORROW, SELECT BORROW AND GRAVEL BORROW ITEMS, THE ORIGINAL GROUND WILL BE COMPARED WITH A SURVEY OF THE EXCAVATION AREA TAKEN AFTER THE WORK IS COMPLETED. WHEN THE CONTRACTING AGENCY REQUIRES EXCAVATED MATERIAL TO BE STOCKPILED, RE-EXCAVATED AND MOVED AGAIN. A SECOND MEASUREMENT WILL BE MADE. ADDING QUANTITY FOR THE SAME ITEM USED IN THE ORIGINAL EXCAVATION. THE SECOND MEASUREMENT WILL BE A COMPARISON OF THE ORIGINAL CROSS-SECTION OF THE STOCKPILE WITH A CROSS-SECTION OF THE STOCKPILE AREA AFTER THE SECOND EXCAVATION IS COMPLETED. FOR UNSUITABLE FOUNDATION EXCAVATION, THE WET VOLUME OF THE SLURRY AT THE BOTTOM OF THE RESERVOIR IS ESTIMATED TO BE 30,000 CY. UNSUITABLE FOUNDATION EXCAVATION VOLUME IS ANTICIPATED TO BE LESS THAN FOOTPRINT SHALL BE INCIDENTAL TO "SMALL SALVAGED TREES." 10,000 CY FOLLOWING DEWATERING, UNSUITABLE FOUNDATION EXCAVATION WILL NOT BE MEASURED AS IT WILL BE PAID AS A LUMP SUM AND SHALL INCLUDE SUBGRADE EXCAVATION FOR SPRAYER PLATFORMS.

11. THE FOLLOWING PROVISIONS IN SECTION 2-03.4 "GRAVEL BORROW AND SELECT BORROW WILL BE MEASURED BY THE CUBIC YARD OR TON, MEASUREMENT BY CUBIC YARD WILL BE MADE IN THE HAULING VEHICLE." SHALL NOT APPLY.

- 12. THE FOLLOWING PROVISIONS IN SECTION 2-03.5 "WHEN THE ENGINEER ORDERS WORK ACCORDING TO SECTION 2-03.3(3), UNIT CONTRACT PRICES SHALL APPLY UNLESS THE WORK DIFFERS MATERIALLY FROM THE EXCAVATION ABOVE SUBGRADE, THEN PAYMENT WILL BE IN ACCORDANCE WITH Section 1-04.4." SHALL NOT APPLY.
- 13. THE FOLLOWING PROVISIONS IN SECTION 2-03.5 "UNSUITABLE FOUNDATION EXCAVATION INCL. HAUL, PER CUBIC YARD" SHALL BE REPLACED BY THE FOLLOWING: "UNSUITABLE FOUNDATION EXCAVATION INCL. HAUL, LUMP SUM.
- 14. THE FOLLOWING PROVISIONS IN SECTION 2-03.5 "UNSUITABLE FOUNDATION EXCAVATION, PER CUBIC YARD", "SELECT BORROW INCL. HAUL, PER TON", AND "GRAVEL BORROW INCL. HAUL, PER TON" SHALL NOT APPLY
- 15. NO WORK SHALL OCCUR OUTSIDE OF THE LIMITS OF DISTURBANCE SHOWN IN THE PLANS UNLESS AUTHORIZED BY THE OWNER.

### MEASUREMENT

COMMON BORROW, SELECT BORROW, STREAMBED GRAVEL INCLUDING HAUL, AND GRAVEL BORROW ITEMS WILL BE MEASURED BY THE CUBIC YARD. PLACEMENT OF SALVAGED ROCK AND EARTH EMBANKMENTS SHALL BE INCIDENTAL TO DAM DEMOLITION, COMMON BORROW, SELECT BORROW AND GRAVEL BORROW ITEMS. COMMON BORROW.

SELECT BORROW AND GRAVEL BORROW MATERIALS WILL BE MEASURED IN THE POSITION IT OCCUPIED BEFORE THE EXCAVATION WAS PERFORMED. COMMON, SELECT AND GRAVEL BORROW MATERIALS SHALL BE SORTED AND STOCKPILED PRIOR TO PLACEMENT. AN ORIGINAL GROUND MEASUREMENT WILL BE TAKEN USING CROSS-SECTION OR DIGITAL TERRAIN MODELING SURVEY TECHNIQUES. SLOPE/GROUND INTERCEPT POINTS DEFINING THE LIMITS OF THE MEASUREMENT WILL BE AS STAKED, FOR COMMON BORROW, SELECT BORROW AND GRAVEL BORROW ITEMS, THE ORIGINAL GROUND WILL BE COMPARED WITH A SURVEY OF THE EXCAVATION AREA TAKEN AFTER THE WORK IS COMPLETED. WHEN THE CONTRACTING AGENCY REQUIRES EXCAVATED MATERIAL TO BE STOCKPILED, RE-EXCAVATED AND MOVED AGAIN, A SECOND MEASUREMENT WILL BE MADE, ADDING QUANTITY FOR THE SAME ITEM USED IN THE ORIGINAL EXCAVATION. THE SECOND MEASUREMENT WILL BE A COMPARISON OF THE ORIGINAL CROSS-SECTION OF THE STOCKPILE WITH A CROSS-SECTION OF THE STOCKPILE AREA AFTER THE SECOND EXCAVATION IS COMPLETED. FOR UNSUITABLE FOUNDATION EXCAVATION, THE WET VOLUME OF THE SLURRY AT THE BOTTOM OF THE RESERVOIR IS ESTIMATED TO BE 30,000 CY. UNSUITABLE FOUNDATION EXCAVATION VOLUME IS ANTICIPATED TO BE 5,000 TO 10,000 CY FOLLOWING DEWATERING. UNSUITABLE FOUNDATION EXCAVATION INCLUDING. HAUL WILL NOT BE MEASURED AS IT WILL BE PAID AS A LUMP SUM AND SHALL INCLUDE SUBGRADE EXCAVATION FOR SPRAYER PLATFORMS.

#### PAYMENT

PAYMENT SHALL BE CONSIDERED FULL COMPENSATION FOR ALL EQUIPMENT, LABOR, TOOLS, MATERIALS, AND INCIDENTALS NECESSARY TO COMPLETE THIS WORK AS SPECIFIED. PAYMENT WILL BE MADE IN ACCORDANCE WITH SECTION 1-04.1 FOR THE FOLLOWING BID ITEMS: "COMMON BORROW INCLUDING. HAUL", "SELECT BORROW INCLUDING. HAUL", "GRAVEL BORROW INCLUDING. HAUL", STREAMBED GRAVEL INCLUDING HAUL, AND "EMBANKMENT COMPACTION" ITEMS WILL BE PAID PER CUBIC YARD. "UNSUITABLE FOUNDATION EXCAVATION INCLUDING HAUL" WILL BE PAID AS A LUMP SUM.

#### ITEM 006 SMALL SALVAGED TREES

### DESCRIPTION

THIS ITEM CONSISTS OF REMOVING TREES 10 TO 20 DBH, INCLUDING ROOTWADS. TOPS AND BROKEN BRANCHES SHALL BE SALVAGED AS SLASH. THIS ITEM SHALL INCLUDE DIGGING AROUND ROOTS AND PUSHING OVER EXISTING TREES, TRANSPORTING SMALL SALVAGED TREES AND PLACING SMALL SALVAGED TREES. SALVAGED TREES SHALL BE LEFT AT THEIR FULL LENGTH, EXCEPT TOPS LESS THAN 6 INCHES IN DIAMETER. STRAW BALES PLACED WITH LARGE WOOD STRUCTURES AND EXCAVATION TO PLACE LARGE WOOD IN THE RESERVOIR AND DAM

#### MEASUREMENT

"SMALL SALVAGED TREES" WILL BE MEASURED BY EACH TREE.

#### PAYMENT

"SMALL SALVAGED TREES" WILL BE PAID FOR ON A PER EACH BASIS.

# ITEM 007 LARGE SALVAGED TREES

#### DESCRIPTION

THIS ITEM CONSISTS OF REMOVING TREES OVER 20 DBH, INCLUDING ROOTWADS. TOPS AND BROKEN BRANCHES SHALL BE SALVAGED AS SLASH. THIS ITEM SHALL INCLUDE DIGGING AROUND ROOTS AND PUSHING OR PULLING OVER EXISTING TREES. TRANSPORTING LARGE SALVAGED TREES AND PLACING LARGE SALVAGED TREES INCLUDING ANCHORING MATERIALS (CHAIN, THREADED REBAR, EXPOXY, NUTS AND WASHERS. SALVAGED TREES SHALL BE LEFT AT THEIR FULL LENGTH, EXCEPT TOPS LESS THAN 6 INCHES IN DIAMETER. STRAW BALES PLACED WITH LARGE WOOD STRUCTURES AND EXCAVATION TO PLACE LARGE WOOD IN WILDBOY CREEK DOWNSTREAM OF THE DAM SHALL BE INCIDENTAL TO "LARGE SALVAGED TREES."

#### MEASUREMENT

"LARGE SALVAGED TREES" WILL BE MEASURED BY EACH TREE. LARGE SALVAGED TREES WILL BE USED AS KEY PIECES IN CHANNEL SPANNING LARGE WOOD STRUCTURES. LARGE SALVAGED TREES MAY BE CUT, AS

APPROVED BY THE ENGINEER. AND USED AS SILL LOGS. ROOT WADS. SLASH OR OTHER CLASSIFICATION USED IN THESE DRAWINGS. NO SEPARATE MEASUREMENT WILL BE MADE FOR HOW LARGE SALVAGED TREES ARE INSTALLED.

#### PAYMENT

**ITEM 008 IMPORTED LOGS** 

### DESCRIPTION

THIS ITEM CONSISTS OF PROVIDING AND INSTALLING LOGS OVER 14 DBH. LOGS USED FOR FLOATING INTAKES AND REUSED AS LARGE WOOD SHALL ONLY BE PAID FOR ONCE.

#### MEASUREMENT

"IMPORTED LOGS" WILL BE MEASURED BY EACH LOG.

#### PAYMENT

"IMPORTED LOGS" WILL BE PAID FOR ON A PER EACH BASIS.

#### DESCRIPTION

THIS ITEM CONSISTS OF INSTALLING LARGE WOOD PROVIDED BY THE OWNER. LARGE WOOD SHALL BE OVER 14 DBH. LOGS USED FOR FLOATING INTAKES AND REUSED AS LARGE WOOD SHALL ONLY BE PAID FOR ONCE.

#### MEASUREMENT

OF LARGE WOOD.

#### PAYMENT

"OWNER PROVIDED LARGE WOOD" WILL BE PAID FOR ON A PER EACH BASIS.

### **ITEM 010 SEEDING**

#### DESCRIPTION

THIS ITEM CONSISTS OF FURNISHING AND PLACING PERMANENT SEED IN ACCORDANCE WITH SECTION 8-01 OF THE STANDARD SPECIFICATIONS, AND AS AMENDED BY THESE SPECIAL PROVISIONS. ANY TEMPORARY SEEDING SHALL BE INCLUDED IN ITEM 001 TESC, SPCC PLAN AND IMPLEMENTATION

#### **MEASUREMENT**

"SEEDING" WILL BE MEASURED PER ACRE.

#### PAYMENT

"NATIVE SEED MIX" PER ACRE ACTUALLY PLACED AT THE CUMULATIVE. AND SPECIES SPECIFIC, LBS/ACRE RATE SPECIFIED ON THE DRAWINGS.

#### **ITEM 011 PLANTING**

### DESCRIPTION

THIS ITEM CONSISTS OF FURNISHING AND PLANTING CUTTINGS, LIVE POLES, AND CONTAINER PLANTS IN ACCORDANCE WITH SECTION 8-02 OF THE STANDARD SPECIFICATIONS, AND AS AMENDED BY THESE SPECIAL PROVISIONS.

- IN ACCORDANCE WITH SECTION 8-02.3(2)B.
- ACCORDANCE WITH SECTION 8-02.3(2)C.

### MEASUREMENT

THE PAY QUANTITIES FOR PLANT MATERIALS WILL BE DETERMINED BY COUNT OF THE NUMBER OF SATISFACTORY PLANTS IN EACH CATEGORY ACCEPTED BY THE ENGINEER.

"LARGE SALVAGED TREES" WILL BE PAID FOR ON A PER EACH BASIS.

# ITEM 009 OWNER PROVIDED LARGE WOOD

"OWNER PROVIDED LARGE WOOD" WILL BE MEASURED BY EACH PIECE

1. THE CONTRACTOR SHALL SUBMIT A WEED AND PEST CONTROL PLAN 2. THE CONTRACTOR SHALL SUBMIT A PLANT ESTABLISHMENT PLAN IN

## PAYMENT

"RED-OSIER DOGWOOD, CUTTING" PER EACH. "SITKA WILLOW, CUTTING" PER EACH. "SCOULER'S WILLOW, CUTTING" PER EACH. "SALMONBERRY, 1-GALLON CONTAINER" PER EACH. "RED ALDER, 1-GALLON CONTAINER" PER EACH. "BIG LEAF MAPLE, 1-GALLON CONTAINER" PER EACH. "MERTEN'S SEDGE, PLUG" PER EACH. "SMALLWING SEDGE, PLUG" PER EACH. "DAGGERLEAF RUSH, PLUG" PER EACH. "DOUGLAS FIR, -GALLON CONTAINER" PER EACH. "WESTERN RED CEDAR, 1-GALLON CONTAINER" PER EACH. "THIMBLEBERRY, 1-GALLON CONTAINER" PER EACH. "SALAL, 1-GALLON CONTAINER" PER EACH. "WESTERN SWORDFERN, 1-GALLON CONTAINER" PER EACH. "WESTERN BRACKENFERN, 1-GALLON CONTAINER" PER EACH.





#### Notes:



# LEGEND

- EXISTING RIVER PATHWAYS
  - EXISTING RESERVOIR
  - EXISTING DAM AND SPILLWAY
  - EXISTING FOREST ROAD
  - PROPOSED TEMPORARY ACCESS ROADS (VEHICLES)
  - PROPOSED TEMPORARY ACCESS ROADS (OFF ROAD)
  - PROJECT BOUNDARY AREA
  - LIMITS OF DISTURBANCE



NOTE: THESE ACCESS ROADS ARE INTENDED FOR TRACKED VEHICLES AND SKIDDERS. ADD GRAVEL FROM DAM CONSTRUCTION SPOILS AS NEEDED

IF SOFT SPOTS DEVELOPE.





RP

5

DRAWING NO

ΒN

80





# LEGEND

- EXISTING RIVER PATHWAYS
  - EXISTING DAM AND SPILLWAY
  - EXISTING FOREST ROAD
  - PROPOSED TEMPORARY ACCESS ROADS (VEHICLES)
  - PROPOSED TEMPORARY ACCESS ROADS (OFF ROAD)
  - PROPOSED ACCESS ROADS (TO REMAIN)
  - PROJECT BOUNDARY AREA
  - PROPOSED TRIBUTARIES
  - EPHEMERAL STREAM
  - LIMITS OF DISTURBANCE
  - STAGING AND STOCKPILE
  - WATER TURBIDITY MONITORS
  - KAYAKERS WARNING SIGNS







NOTE : ALL STAGING AND STOCKPILE AREAS TO BE CLEARED AND GRUBBED.

RESERVOIR OHW AREA = 10.83 ACRES



REV: DESCRIPTION: BY: DATE: STATUS: PRELIMINARY DESIGN



COWLITZ INDIAN TRIBE 7700 26TH AVE VANCOUVER, WA, 98665

#### KWONEESUM DAM REMOVAL DESIGN

TITLE:

#### SITE PREPARATION, CLEARING AND GRUBBING

| SCALE:    | DATE:       | DRAWN: | CHECKED:      |
|-----------|-------------|--------|---------------|
|           | 6/4/21      | RP     | BN            |
| PROJ. NO: | DRAWING NO: |        | Total Sheets: |
| -         |             | 7      | 80            |



# CONSTRUCTION SEQUENCE

- CLEAR AND GRUB DAM CONSTRUCTION SPOILS PILE. EXCAVATE AND SORT 1. DAM CONSTRUCTION SPOILS PILE INTO BOULDERS, COBBLE, GRAVEL, AND SOIL. STEP 1 IN THIS SEQUENCE WILL BE PERFORMED UNDER A SEPARATE CONTRACT PRIOR TO THE DAM REMOVAL CONTRACT. SEPARATE PILES OF BOULDERS. COBBLE. GRAVEL AND SOIL WILL BE LOCATED IN THE STAGING AND STOCKPILE AREA LOCATED SOUTHEAST OF THE RESERVOIR.
- 2 CLEAR AND GRUB STAGING AREAS. ACCESS ROADS. INCLUDING ACCESS AROUND THE RESERVOIR TO TRIBUTARY DIVERSION LOCATIONS, TEXAS CREEK DISCHARGE LOCATIONS, AND WILDBOY CREEK ACCESS LOCATIONS DOWNSTREAM OF DAM.
- PLACE BLIND FLANGES AND GASKETS ON ENDS OF WELDED JOINT HDPE PIPE 3 TO FLOAT DIVERSION PIPING CLOSE TO TRIBUTARY DIVERSION DAM LOCATIONS AT FULL RESERVOIR LEVEL. DRAG WELDED JOINT HDPE PIPING OUT OF THE WATER. WITH BLOCK AND TACKLE AND OTHER EQUIPMENT TO UPSTREAM END OF DIVERSION DAM LOCATIONS IN TRIBUTARIES, IDENTIFIED ON THE DRAWINGS. INSTALL TRIBUTARY DIVERSION PIPING FROM TRIBUTARY DIVERSION LOCATIONS TO TEXAS CREEK.
- INSTALL TRIBUTARY DIVERSION DAMS AND PERFORM FISH EXCLUSION 4 UPSTREAM OF DIVERSION DAMS. PLACE SCREENED PUMP INTAKES, PUMPS, GENERATORS, AND SPILL CONTAINMENT MEASURES. PLACE PUMPED OUTLET EROSION CONTROL MEASURES IN TEXAS CREEK PRIOR TO INITIATING PUMPED TRIBUTARY DIVERSIONS.
- AN EXPERIENCED BIOLOGIST WILL LEAD A TEAM THAT BEGINS CLEARING FISH 3-5 DAYS PRIOR TO DIVERTING TRIBUTARY FLOWS. THE COWLITZ TRIBE EXPECTS TO HAVE MULTIPLE ELECTRO-FISHING CREWS AND WDFW VOLUNTEERS TO CLEAR THE 0.25 MILE REACH DOWNSTREAM OF THE DAM. ALL COLLECTED FISH AND AMPHIBIANS WILL BE SPECIATED AND ENUMERATED. AN INITIAL FISH RESCUE PASS WILL BE PERFORMED IN THE 0.25 MILE LONG REACH DOWNSTREAM OF THE DAM TO THE EXISTING SPRING LOCATED NEAR THE LEFT BANK OR WILDBOY CREEK. FISH CLEARING WILL OCCUR IN DEFINED SECTIONS/SUB REACHES BY USING SEINES AS BLOCK NETS
- DIVERT TRIBUTARY FLOWS EARLY IN THE MORNING TO CONCENTRATE 6. REMAINING FISH IN RESIDUAL POOLS IN THE 0.25 MILE REACH DOWNSTREAM OF THE DAM. SIMULTANEOUSLY, BEGIN THE SECOND ROUND OF FISH CLEARING AS THE 0.25 MILE REACH DOWNSTREAM OF THE DAM BEGINS TO DEWATER. THE CONTRACTOR SHALL ASSIST BY PUMPING DOWN EACH RESIDUAL POOL WITH A NMFS APPROVED SCREENED INTAKE WHILE FISH RESCUE IS PERFORMED IN EACH REMAINING POOL. THE COWLITZ TRIBE EXPECTS TO HAVE MULTIPLE ELECTRO-FISHING CREWS AND WDFW VOLUNTEERS TO CLEAR THE 0.25 MILE REACH DOWNSTREAM OF THE DAM. ALL COLLECTED FISH AND AMPHIBIANS WILL BE SPECIATED AND ENUMERATED. THE SECOND PASS OF FISH CLEARING IS EXPECTED TO TAKE AN ADDITIONAL 2-4 DAYS TO FULLY CLEAR FISH FROM THE 0.25 REACH DOWNSTREAM OF THE DAM.
- AFTER FISH ARE CLEARED FROM THE 0.25 MILE REACH DOWNSTREAM OF THE DAM, BEGIN CLEARING FISH FROM THE 0.25 MILE REACH FROM THE EXISTING SPRING TO THE CONFLUENCE WITH TEXAS CREEK. THE FIRST PASS OF FISH CLEARING WILL OCCUR IN THIS REACH WHILE THE SPRING IS STILL FLOWING TO THE CONFLUENCE WITH TEXAS CREEK. FISH CLEARING WILL OCCUR IN DEFINED SECTIONS/SUB REACHES BY USING SEINES AS BLOCK NETS. THE COWLITZ TRIBE EXPECTS TO HAVE MULTIPLE ELECTRO-FISHING CREWS AND WDFW VOLUNTEERS TO CLEAR THE 0.25 MILE REACH TO TEXAS CREEK. ALL COLLECTED FISH AND AMPHIBIANS WILL BE SPECIATED AND ENUMERATED. THE FISH CLEARING IS EXPECTED TO TAKE AN ADDITIONAL 3-5 DAYS TO FULLY CLEAR FISH FROM THE 0.25 REACH TO THE CONFLUENCE WITH TEXAS CREEK
- INSTALL A SANDBAG DAM TO FORM A SPRING COLLECTION POOL DOWNSTREAM OF THE SPRING AND INSTALL A GRAVITY PIPELINE ALONG THE BANK OF WILDBOY CREEK TO CONVEY WATER TO DOWNSTREAM OF THE CONFLUENCE WITH TEXAS CREEK. DEWATER THE 0.25 MILE REACH FROM THE EXISTING SPRING TO THE CONFLUENCE WITH TEXAS CREEK AND PERFORM A SECOND PASS OF FISH CLEARING CONCURRENTLY. THE CONTRACTOR SHALL ASSIST BY PUMPING DOWN EACH RESIDUAL POOL WITH A NMFS APPROVED SCREENED INTAKE WHILE FISH RESCUE IS PERFORMED IN EACH REMAINING POOL. INSTALL BLOCK NETS JUST UPSTREAM OF TEXAS CREEK IF NEEDED.
- PLACE SILT CURTAIN IN RESERVOIR. PLACE FLOATING INTAKES, PUMPS AND DEWATERING FIELD SPRAYERS TO PREPARE FOR INITIAL DRAWDOWN. PLACE CLEAR WATER PUMP ON THE DAM FACE TO PREPARE FOR INITIAL DRAWDOWN. THE FLOATING INTAKES ARE INTENDED TO INTERCEPT TURBID WATER GENERATED ALONG SHORELINES DURING INITIAL DRAWDOWN. FLOWS PUMPED FROM THE FLOATING INTAKES WILL BE CONVEYED TO DEWATERING FIELD SPRAYERS FOR LAND APPLICATION AND INFILTRATION

- 10. COMMENCE CLEAR WATER DIVERSION PUMPING, AND FLOATING INTAKE PUMPING. THE CONTRACTOR SHALL MONITOR SPRAY LOCATIONS IN THE DEWATERING FIELD AND THROTTLE DOWN PUMPED FLOWS TO AVOID SURFACE RUNOFF. THE CLEAR WATER PUMP WILL PUMP WATER FROM DEEPER PORTIONS OF THE RESERVOIR OVER THE DAM. WHILE ASSURING THE CLEARWATER PUMP'S INTAKE IS SUFFICIENTLY ABOVE FINE SEDIMENTS LOCATED AT THE BOTTOM OF THE RESERVOIR TO AVOID MOBILIZING THOSE SEDIMENTS. FLOATING INTAKE PUMPS WILL OPERATE AT A SLIGHTLY HIGHER CUMULATIVE FLOW RATE THAN THE CLEAR WATER PUMP TO AVOID TURBID WATER FROM PASSING UNDER THE SILT CURTAIN.
- 11. MONITOR TURBIDITY PLUMES IN THE RESERVOIR AND ADJUST LINES SECURING TURBIDITY CURTAIN AND FLOATING INTAKES AS RESERVOIR LEVELS DESCEND. ADJUST LOCATION OF TURBIDITY CURTAIN AND FLOATING INTAKES, AS NECESSARY TO AVOID DISTURBING RESERVOIR SEDIMENTS. CONTINUE TO MONITOR TURBIDITY PLUMES DURING INITIAL DRAWN DOWN. INITIAL DRAW DOWN OF MORE THAN 10 FEET WILL SIGNIFICANTLY REDUCE EVAPORATIVE DEWATERING DURATION. TEN FEET OF DRAW DOWN CAN BE ACHIEVED IN TEN DAYS (12 HR/DAY) OPERATION DURING DRY WEATHER CONDITIONS IF DIVERSION DAMS AND PIPING ARE PROPERLY SEALED, NO MAJOR SPRINGS ARE LOCATED WITHIN THE RESERVOIR, AND THE CONTRACTOR AVOIDS STIRRING UP BOTTOM SEDIMENTS.
- 12. PARTIALLY DEMOLISH CONCRETE DAM FACE AND CREATE A LEVEL PLATFORM TO MOVE CLEARWATER PUMP DOWN DAM FACE TO REDUCE SUCTION HEAD AS NECESSARY AS RESERVOIR LEVELS DESCEND. CONTINUE TO MONITOR TURBIDITY PLUMES IN THE RESERVOIR DURING INITIAL DRAWN DOWN. CEASE CLEARWATER PUMPING BEFORE TURBIDITY PLUMES ENTER THE CLEARWATER PUMP INTAKE.
- 13. AFTER CLEARWATER PUMPING HAS CEASED, REMOVE THE SILT CURTAIN AND PERFORM FISH RESCUE WITHIN THE RESERVOIR. FLOATING INTAKES SHALL REMAIN IN THE RESERVOIR DURING FISH RESCUE. REMOVE CLEARWATER PUMP. CONTRACTOR SHALL CLEAR SOFT SOILS FROM THE DEWATERED SHORELINE FOR BOAT TRAILER ACCESS AND ASSIST WDEW IN DEPLOYING AND RETRIEVING ELECTROFISHING BOAT.
- 14. THE CONTRACTOR SHALL RELOCATE FLOATING INTAKES TO DEEPER PORTIONS OF THE RESERVOIR AND CONTINUE TO PUMP TO THE DEWATERING FIELD AS LONG AS FLOATING INTAKES ARE 2-FEET, MINIMUM, ABOVE FINE SEDIMENTS LOCATED AT THE BOTTOM OF THE RESERVOIR.
- 15. LARGE WOOD STRUCTURES IN WILDBOY CREEK (SHEETS 57-71) DOWNSTREAM OF KWONEESUM DAM MAY BE CONSTRUCTED CONCURRENTLY WITH STEPS 15 THROUGH 20 OF THIS SEQUENCE, NOTING THAT ROCK SALVAGED FROM DAM MAY BE INSTALLED AFTER LARGE WOOD AND SLASH HAVE BEEN INSTALLED IN THE LARGE WOOD STRUCTURES.
- 16. DAM DEMOLITION CAN COMMENCE FROM THE TOP DOWN AS LONG AS 10 FEET OF FREEBOARD IS MAINTAINED. REMOVE REBAR AND STOCKPILE DEMOLISHED CONCRETE. RELOCATE PUMPS AND CONTAINMENT IF ALLOWABLE SUCTION HEAD IS EXCEEDED.
- 17. PERFORM EVAPORATIVE DEWATERING OF THE RESERVOIR, (SHEETS 20-23).
- 18. CONTINUE DAM DEMOLITION WHILE MAINTAINING 10 FEET, MINIMUM FREEBOARD UNTIL FINE SEDIMENT HAVE BEEN RELOCATED. ESTABLISH ACCESS ROUTES WITHIN THE RESERVOIR FOOTPRINT USING SPOILS FROM DAM DEMOLITION FOR ACCESS ROAD FILL. REMOVE FINE SEDIMENT AND PLACE IN DISPOSAL AREAS WHICH USE ACCESS ROADS FOR CONTAINMENT.
- 19. INSTALL DEWATERING COFFERDAM 1 UPSTREAM OF DAM AND PUMP WATER AND PERFORM FISH RESCUE IN THE PLUNGE POOL DOWNSTREAM OF THE DAM PRIOR TO REMOVING BOTTOM 10 FEET OF CONCRETE APRON AT THE UPSTREAM FACE OF DAM, SHEET 28. AFTER FINE SEDIMENT HAS BEEN RELOCATED TO CONFINED AREAS OF THE FORMER RESERVOIR AND ALLOWED TO DRAIN, MIX WITH SOIL SALVAGED FROM ORIGINAL DAM CONSTRUCTION SPOILS AS REFERENCED IN STEP 1 OF THIS SEQUENCE. THE DRAINED AND MIXED SOILS SHALL BE SPREAD IN UNCONFINED AREAS OF THE RESERVOIR, OUTSIDE OF STREAM CHANNEL ALIGNMENTS.
- 20. SALVAGE AND STOCKPILE DELTAIC SEDIMENTS (SAND AND GRAVEL) FOR CHANNEL CONSTRUCTION. STAGE AND STOCKPILE ROCK SALVAGED FROM DAM AND SPILLWAY DEMOLITION THAT WILL BE USED FOR LARGE WOOD STRUCTURE CONSTRUCTION AND OTHER PURPOSES.
- 21. USE DEWATERING COFFERDAM 1 TO COMPLETELY REMOVE DAM AND CONSTRUCT WILDBOY CREEK CHANNEL WITHIN FORMER DAM FOOTPRINT. USE THE PLUNGE POOL (DOWNSTREAM OF THE FORMER DAM) AS A SEDIMENT TRAP AFTER CHANNEL IS CONSTRUCTED WITHIN FORMER DAM FOOTPRINT. TURBID WATER COLLECTED IN THE PLUNGE POOL SHALL BE PUMPED TO SPRAYERS LOCATED IN CLEARCUT AREAS FOR INFILTRATION AS DESCRIBED FOR INITIAL DRAWDOWN. ALTERNATE USE OF DEWATERING COFFERDAM 1 AND PLUNGE POOL DEWATERING, AS NECESSARY TO CONSTRUCT TRIBUTARY CHANNELS WITHIN THE RESERVOIR

- 22. AFTER CHANNELS HAVE BEEN CONSTRUCTED WITHIN THE RESERVOIR, REINTRODUCE TRIBUTARY FLOWS, ONE AT A TIME TO FLUSH SEDIMENT FROM EACH CONSTRUCTED TRIBUTARY CHANNEL. THE ABILITY TO PUMP FROM EACH TRIBUTARY DIVERSION SHALL REMAIN INTACT UNTIL ALL CHANNELS HAVE BEEN FLUSHED. ONE AT A TIME. INITIAL FLUSHING OF TRIBUTARY CHANNELS SHALL BE COLLECTED IN THE PLUNGE POOL DOWNSTREAM OF THE FORMER DAM LOCATION AND PUMPED TO SPRAYERS IN CLEARCUTS FOR INFILTRATION AS DESCRIBED FOR INITIAL DRAWDOWN. AFTER ALL TRIBUTARIES HAVE BEEN FLUSHED ONE AT A TIME. SUBSEQUENTLY REMOVE TRIBUTARY DIVERSION DAM AND PIPING FOR EACH TRIBUTARY AND ALLOW FLOW THROUGH THE PROJECT.
- 23. PLACE SEEDING AND MULCH IN DISTURBED AREAS.
- 24. PERFORM FINAL SITE STABILIZATION.









|                      | 6/4/21 RP BN      |             |          |  |  |  |
|----------------------|-------------------|-------------|----------|--|--|--|
| ALE:                 | DATE:             | DRAWN:      | CHECKED: |  |  |  |
| WATER DIVERSION PLAN |                   |             |          |  |  |  |
|                      | AND DAM - SURFACE |             |          |  |  |  |
| 1.1                  | 1 OT 1 L L J C    | NAL INCOLIN | V OIR    |  |  |  |













2 - · · · 1 - · · · REV: DESCRIPTION: BY: DATE: STATUS: PRELIMINARY DESIGN



COWLITZ INDIAN TRIBE 7700 26TH AVE VANCOUVER, WA, 98665

### KWONEESUM DAM REMOVAL DESIGN



CONTRACTOR SHALL ESTABLISH ACCESS FOLLOWING INITIAL DRAWDOWN AND ASSIST WITH LAUNCHING AND TRAILERING WDFW ELECTROFISHING BOAT

CAMP KWONEESUN

> DRVERSION PIPE 5 CROSSING, TYP 18

> > STAGING AND

TRIBUTARY HDPE DIVERSION PIPES PUMPED TO TEXAS CREEK



#### Notes:

- 12 IN. HDPE WELDED JOINT SDR-17

- FINE SEDIMENT AREA AFTER INITIAL







REV: DESCRIPTION: BY: DATE: STATUS: PRELIMINARY DESIGN



COWLITZ INDIAN TRIBE 7700 26TH AVE /ANCOUVER, WA, 98665

TITLE:

KWONEESUM DAM REMOVAL DESIGN

#### KWONEESUM RESERVOIR AND DAM - INITIAL DRAWDOWN PLAN

| SCALE:    | DATE:       | DRAWN: | CHECKED:      |
|-----------|-------------|--------|---------------|
|           | 6/4/21      | RP     | BN            |
| PROJ. NO: | DRAWING NO: |        | Total Sheets: |
| -         |             | 4      | 80            |







TURBIDITY ( CURTAIN 19

-SECURE WIRE ROPE TO TURBIDITY CURTAIN/FLOATING INTAKE

-DIVERSION PIPE







-12 IN. FLOTATION

#### REV: DESCRIPTION: BY: DATE: STATUS: PRELIMINARY DESIGN exce lence 302 W. Steuben St. #6 Bingen, WA 98605 www.ers4life.com CLIENT COWLITZ INDIAN TRIBE 7700 26TH AVE VANCOUVER, WA, 98665 KWONEESUM DAM **REMOVAL DESIGN** TITLE: KWONEESUM RESERVOIR AND DAM - DEWATERING TYPICAL DETAILS SCALE: DATE: CKED 6/4/21 RP ΒN DRAWING NO: PROJ. NO: tal Sheets 80 19 -





#### DETAIL - FLANGE ADAPTER AND BACK-UP RING



#### **DETAIL - BOLT LENGTH PARAMETERS**

| IPS<br>PIPE<br>SIZE | FLANGE<br>OD | BOLT<br>PIPE<br>DIAMEER | BOLT<br>HOLE<br>DIAMETER | NO.<br>OF<br>BOLTS |
|---------------------|--------------|-------------------------|--------------------------|--------------------|
| 6                   | 11.00        | 9.50                    | 0.88                     | 8                  |
| 8                   | 13.50        | 11.75                   | 0.88                     | 8                  |
| 18                  | 25.00        | 22.75                   | 1.25                     | 16                 |
| 24                  | 32.00        | 29.50                   | 1.38                     | 20                 |

#### TABLE - FLANGE DIMENSIONS (INCH SIZED) ANSI B16.5 CLASS 150

### **TYPICAL DETAIL - FLANGE ADAPTER AND BACKUP RING**

 $\begin{pmatrix} 1 \\ 21 \end{pmatrix}$ 

# NOT TO SCALE



**DETAIL - FLANGE CONNECTION TO SPRAYER PLATFORM** 



8

### **DETAIL - FLANGE GASKET STYLES**



FULL FACE STYLE





 $\frac{-3}{4}$  IN. DIA., ALL THREAD ASTM A307, GRADE A EMBEDDED 6 IN. MIN. ADHERE WITH HILTI HIT RE 500, OR APPROVED EQUAL. STEEL WASHER AND NUT FASTENERS,

-6 IN. HDPE FLANGED PIPE END BOLTED TO BOTTOMOF  $\frac{1}{2}$  IN. THICK, STEEL PLATE.

–4 IN. MALE NTP. WELDED CONNECTION TO STEEL PLATE

-6 IN. HDPE PIPE

-6 IN. HDPE PIPE FROM PUMP

R12.5 FT (MIN.)

-EXCAVATE ADJACENT GROUND SURFACE TO MAINTAIN 13 FT. MIN PIPE





-PLACE EXISTING RIPRAP EXCAVATED FOR GRAVITY DIVERSION PIPE INSIDE OF NORTHWEST CORNER OF OGEE CREST. RIPRAP MATERIAL SHALL BE PLACED INDIVIDUALLY AND IN LIFTS OF HALF THE RIPRAP HEIGHT THICKNESS. EACH LIFT OF RIPRAP SHALL BE FILLED WITH SMALL (3-INCH, MINUS) REMOVED FROM THE DAM BEFORE THE NEXT LIFT OF RIPRAP IS PLACED. CONTRACTOR SHALL COMPACT MATERIALS WITH EXCAVATOR BUCKET AND TRACKS FOR EACH SUCCESSIVE LIFT. SUBSEQUENT LIFTS OF RIPRAP SHALL BE PLACED IN SUCH A WAY THAT POCKETS BETWEEN OR UNDER THEM CAN BE FILLED WITH CRUSHED ROCK FROM THE DAM EITHER BEFORE OR AFTER RIPRAP PLACEMENT. ADD GRAVEL BASE AND CRUSHED SURFACING BASE PER DETAIL 1 OF SHEET 16 OVER RIPRAP LIFTS.













NOT TO SCALE









- - EXISTING DAM TO BE REMOVED

