
Exhibit G Project Plans



LOCKED

KWONEESUM DAM


FINAL REMOVAL DESIGN SKAMANIA COUNTY, WASHINGTON NOVEMBER 17, 2023

SHEET INDEX

- 1 COVER, SHEET INDEX, AND PROJECT LOCATION
- 2 GENERAL NOTES
- 3 GENERAL NOTES
- 4 PROJECT AREA AND SITE MAP
- 5 PROJECT INDEX MAP
- 6 SITE PREPARATION, CLEARING AND GRUBBING
- 7 KWONEESUM RESERVOIR & DAM EXISTING CONDITIONS
- 8 CONSTRUCTION SEQUENCE NOTES
- 9 KWONEESUM RESERVOIR & DAM CONSTRUCTION SEQUENCE
- 10 KWONEESUM RESERVOIR & DAM INITIAL DRAWDOWN SITE PLAN
- 11 KWONEESUM RESERVOIR & DAM TEMPORARY STREAM DIVERSION PLAN
- 12 KWONEESUM RESERVOIR & DAM INITIAL
- 13 KWONEESUM RESERVOIR & DAM INITIAL DRAWDOWN PLAN
- 14 KWONEESUM RESERVOIR & DAM DEWATERING TYPICAL DETAILS
- 15 KWONEESUM RESERVOIR & DAM DEWATERING TYPICAL DETAILS
- 16 KWONEESUM RESERVOIR & DAM DEWATERING TYPICAL DETAILS
- 17 KWONEESUM RESERVOIR & DAM DEWATERING TYPICAL DETAILS
- 18 KWONEESUM RESERVOIR & DAM TEMP. STREAM DIVERSION TYP. DETAILS
- 19 KWONEESUM RESERVOIR & DAM DEWATERING TYPICAL DETAILS
- 20 KWONEESUM RESERVOIR & DAM SEDIMENT MANAGEMENT TYPICAL DETAIL
- 21 KWONEESUM RESERVOIR & DAM SEDIMENT MANAGEMENT TYPICAL DETAIL
- 22 KWONEESUM RESERVOIR & DAM ANTICIPATED RESERVOIR MASS GRADING
- 23 KWONEESUM RESERVOIR & DAM MASS GRADING CROSS-SECTIONS 24 - KWONEESUM RESERVOIR & DAM – MASS
- GRADING CROSS-SECTIONS
- 25 KWONEESUM DAM TYPICAL DETAILS DAM REMOVAL
- 26 KWONEESUM DAM DAM REMOVAL
- 27 KWONEESUM DAM DAM REMOVAL SEQUENCE
- 28 KWONEESUM DAM DAM SUBGRADE CROSS-SECTIONS
- 29 KWONEESUM DAM DAM SUBGRADE CROSS-SECTIONS
- 30 KWONEESUM DAM DAM REMOVAL AREA GRADING PLAN
- 31 KWONEESUM DAM DAM REMOVAL AREA LARGE WOOD

- 32 KWONEESUM DAM DAM REMOVAL AREA
- 33 KWONEESUM DAM DAM REMOVAL AREA
- 34 KWONEESUM RESERVOIR NORTH TRIB. GRADING PLAN & PROFILE
- 35 KWONEESUM RESERVOIR NORTH TRIB. LARGE WOOD
- 36 KWONEESUM RESERVOIR NORTH TRIB. GRADING CROSS-SECTIONS
- 37 KWONEESUM RESERVOIR NORTH TRIB. GRADING CROSS-SECTIONS
- 38 KWONEESUM RESERVOIR EAST TRIB. GRADING PLAN & PROFILE
- 39 KWONEESUM RESERVOIR EAST TRIB. LARGE WOOD
- 40 KWONEESUM RESERVOIR EAST TRIB. GRADING CROSS-SECTIONS
- 41 KWONEESUM RESERVOIR EAST TRIB. GRADING CROSS-SECTIONS
- 42 KWONEESUM RESERVOIR WEST TRIB. GRADING PLAN & PROFILE
- 43 KWONEESUM RESERVOIR WEST TRIB. LARGE WOOD
- 44 KWONEESUM RESERVOIR WEST TRIB. GRADING CROSS-SECTIONS
- 45 KWONEESUM RESERVOIR WEST TRIB. GRADING CROSS-SECTIONS
- 46 KWONEESUM RESERVOIR TYPICAL LARGE WOOD
- 47 KWONEESUM DAM SPILLWAY PLAN & PROFILE
- 48 KWONEESUM DAM SPILLWAY CROSS-SECTIONS
- 49 KWONEESUM RESERVOIR EPHEMERAL TRIB. PLAN VIEW
- 50 KWONEESUM RESERVOIR EPHEMERAL TRIB CROSS-SECTIONS
- 51 ON-SITE STOCKPILE PLAN VIEW AND QUANTITIES
- 52 WILDBOY CREEK EXISTING CONDITIONS
- 53 WILDBOY CREEK LARGE WOOD STRUCTURES
- 54 WILDBOY CREEK PROPOSED CONDITIONS
- 55 WILDBOY CREEK PLAN AND PROFILE STA. 0+00 TO 5+00
- 56 WILDBOY CREEK PLAN AND PROFILE STA. 5+00 TO 10+00 57 - WILDBOY CREEK - PLAN AND PROFILE STA. 10+00 TO 15+00
- 58 WILDBOY CREEK PLAN AND PROFILE STA. 15+00 TO 20+00
- 59 WILDBOY CREEK PLAN AND PROFILE STA. 20+00 TO 25+00
- 60 WILDBOY CREEK PLAN AND PROFILE STA. 25+00 TO 30+00
- 61 WILDBOY CREEK PLAN AND PROFILE STA. 30+00 TO 35+00
- 62 WILDBOY CREEK LOG JAM QUANTITIES
- 63 WILDBOY CREEK TYPICAL LARGE WOOD CROSS-SECTIONS
- 64 WILDBOY CREEK TYPICAL LARGE WOOD CROSS-SECTIONS
- 65 WILDBOY CREEK TYPICAL LARGE WOOD CROSS-SECTIONS
- 66 WILDBOY CREEK TYPICAL LARGE WOOD CROSS-SECTIONS

- 68 TYPICAL DETAILS
- 69 TYPICAL DETAILS
- 70 TYPICAL DETAILS
- 71 TYPICAL DETAILS
- 72 TYPICAL DETAILS
- 73 TYPICAL DETAILS
- 74 KWONEESUM RESERVOIR AND WILDBOY CREEK -SEEDING PLAN







KWONEESUM DAM REMOVAL DESIGN

TITLE:

COVER, SHEET INDEX, AND PROJECT LOCATION

SCALE:	DATE:	DRAWN:	CHECKED:
	11/17/23	RP	BN
PROJ. NO:	DRAWING NO:		Total Sheets:
-		1	74

GENERAL NOTES

- THE CONTRACTOR SHALL ATTEND A MANDATORY PRE-BID SITE
 MEETING
- THE CONTRACTOR SHALL ATTEND A PRE-CONSTRUCTION MEETING WITH OWNER PRIOR TO BEGINNING CONSTRUCTION.
- 3. ALL WORK SHALL CONFORM TO THE CURRENT EDITIONS OF STANDARD PLANS AND SPECIFICATIONS OF THE 2023 WASHINGTON STATE DEPARTMENT OF TRANSPORTATION (WSDOT), AND LOCAL STANDARDS UNLESS INDICATED OTHERWISE BY THE CONTRACT DOCUMENTS. IN CASE OF A CONFLICT BETWEEN THE REGULATORY STANDARDS OR SPECIFICATIONS, THE MORE STRINGENT WILL PREVAIL.

WDFW IN-WATER WORK PERIODS

- IN-WATER WORK SHALL OCCUR DURING THE PERMITTED IN-WATER WORK PERIOD STATED IN THE HYDRAULIC PROJECT APPROVAL.
- IN-WATER WORK PERIOD FOR 2024 IS MAY 15TH TO SEPTEMBER 30TH.

EXISTING DATA

- 1. TOPOGRAPHIC DATA COLLECTED BY PARR EXCELLENCE USING RTK, TOTAL STATION, HYDROLITE (SONAR) AND DRONE BASED SFM FROM OCTOBER TO NOVEMBER 2018 AND SPRING 2023; GIS DATA PROVIDED BY VARIOUS AGENCIES INCLUDING AERIAL PHOTOGRAPHY, LIDAR, FISH USE, SURFACE SOILS INFORMATION, LAND OWNERSHIP, AND TRANSPORTATION ROUTES.
- EXISTING DAM INFORMATION INCLUDED IN DEPARTMENT OF ECOLOGY DAM SAFETY REPORT (2006) INCLUDED SCANS OF DESIGN PLANS AND CH2M HILL SKETCH OF PRE-DAM TOPOGRAPHY.
- 3. HORIZONTAL DATUM: NAD83 WASHINGTON STATE PLANES, SOUTH ZONE, US FOOT
- 4. VERTICAL DATUM: NAVD88
- 5. HISTORICAL PHOTOS PROVIDED AS SUPPLEMENTAL INFORMATION. SEE GEODESIGN REPORT PROVIDED AS SUPPLEMENTAL INFORMATION.

SOILS

- RESERVOIR SOILS WERE HIGHLY DISTURBED DURING DAM CONSTRUCTION, SEE HISTORICAL PHOTOS PROVIDED AS SUPPLEMENTAL INFORMATION. SEE GEODESIGN REPORT PROVIDED AS SUPPLEMENTAL INFORMATION.
- SUBSURFACE SOILS ARE EXPECTED TO BE SILT, CLAY, SAND AND GRAVEL. CONTRACTOR SHALL CONDUCT OWN INVESTIGATIONS IF ADDITIONAL DATA IS REQUIRED AT NO ADDITIONAL COST.
- SOILS ON SITE ARE MAPPED AS KINNEY LOAM (MAP UNITS 57, 58, & 59) AND WATER (MAP UNIT 177)
- 4. HTTPS://WEBSOILSURVEY.SC.EGOV.USDA.GOV
- 5. NON-SOIL DEBRIS MAY BE PRESENT IN EXCAVATION AREAS.

UTILITIES

- 1. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR HAVING UTILITIES LOCATED PRIOR TO CONSTRUCTION ACTIVITIES.
- 2. THE CONTRACTOR SHALL CALL (800-424-5555) FOR UTILITY LOCATE PRIOR TO CONSTRUCTION.
- 3. THE CONTRACTOR SHALL IMMEDIATELY CONTACT THE AFFECTED UTILITY SERVICE TO REPORT ANY DAMAGED OR DESTROYED UTILITIES.
- 4. THE CONTRACTOR SHALL PROVIDE EQUIPMENT OR LABOR TO AID THE AFFECTED UTILITY SERVICE IN REPAIRING DAMAGED OR DESTROYED UTILITIES AT NO ADDITIONAL COST.

CONSTRUCTION ACCESS

- ACCESS ROAD ALIGNMENTS WILL BE FLAGGED IN THE FIELD AND
 APPROVED PRIOR TO CLEARING. MINOR REROUTING OF ACCESS
 ROADS WILL OCCUR TO AVOID IMPACTING TREES GREATER THAN
 12 INCH DBH.
- ALL SAPLINGS AND TREES TO BE TRANSPLANTED OR REMOVED SHALL BE CLEARLY MARKED AND APPROVED BY THE OWNER.
- ALL EQUIPMENT, MATERIALS AND PERSONNEL SHALL REMAIN WITHIN THE LIMITS OF DISTURBANCE. ACCESS LOCATIONS AND ALIGNMENTS MAY CHANGE WITHIN THE LIMITS OF DISTURBANCE ONLY IF APPROVED IN WRITING BY OWNER.
- 4. THE CONTRACTOR SHALL KEEP THE WORK AREAS IN NEAT CONDITION, FREE OF DEBRIS AND LITTER FOR THE DURATION OF THE PROJECT.
- ALL DISTURBED AREAS INCLUDING ROADS, DRIVEWAYS AND ACCESS ROUTES SHALL BE RESTORED TO ORIGINAL CONDITION OR BETTER AND RE-VEGETATED PER PLANS.

EROSION CONTROL

 CONTRACTOR SHALL BE SOLELY RESPONSIBLE AT OWN EXPENSE FOR PROVIDING AND MAINTAINING ALL NECESSARY EROSION CONTROL FACILITIES TO COMPLY WITH APPLICABLE EROSION CONTROL REGULATIONS AND TO MAINTAIN CLEAN ACCESS ROUTES.

CONSTRUCTION STAKING

- OWNER WILL PROVIDE STAKING, GRADE STAKES, AND ELEVATION CONTROL POINTS. SOME FIELD ADJUSTMENTS TO THE LINES AND GRADES ARE TO BE EXPECTED.
- THE CONTRACTOR SHALL REPLACE DAMAGED OR DESTROYED CONSTRUCTION STAKES AT NO ADDITIONAL COST.

CONSTRUCTION MATERIALS

- CONTRACTOR SHALL ALLOW FOR EXPANSION OF EXCAVATED MATERIAL AND COMPACTION OF PLACED MATERIAL AT NO ADDITIONAL MEASURE OR COST. MEASUREMENT AND PAYMENT SHALL NOT BE BASED ON WEIGHT TICKETS OR TRUCK MEASURE WITHOUT PRIOR WRITTEN APPROVAL.
- CONTRACTOR SHALL ANTICIPATE AND ASSUME FIT-IN-THE-FIELD APPROACH TO STREAM RESTORATION TASKS. LOCATION, ALIGNMENT, AND ELEVATION ARE SUBJECT TO ADJUSTMENT BASED ON FIELD CONDITIONS, ENCOUNTERED BEDROCK, AND MATERIAL SIZE.
- ANY EXCESS MATERIAL SHALL BE STOCKPILED NEATLY IN AN APPROVED LOCATION OF THE STOCKPILE AND STAGING AREA.

TREE SALVAGE

- VEGETATION REMOVED FROM TEMPORARILY DISTURBED AREAS, INCLUDING TEMPORARY ACCESS ROADS/ROUTES, SHALL BE SALVAGED, STOCKPILED AND RE-USED FOR DECOMMISSIONING OF THOSE AREAS OR INCORPORATED INTO LARGE WOOD STRUCTURES, OR PLACED AS FLOODPLAIN WOOD AS DIRECTED BY THE OWNER.

 3.
- REMOVED VEGETATION, INCLUDING TREES UP TO 12" DBH SHALL BE INCORPORATED INTO LARGE WOOD STRUCTURES AS SLASH AT NO ADDITIONAL COST. VEGETATION LARGER THAN 12" DIAMETER AND 30' LENGTH SHALL BE USED AS STRUCTURAL ELEMENTS. SMALLER MATERIAL SHALL BE USED AS SLASH.
- 8. SELECT SALVAGED, SMALL TREES REMOVED WITHIN CLEARING LIMITS SHALL BE REMOVED WHOLE WITH ROOT WAD AND USED IN RESTORATION CONSTRUCTION. SELECT, LARGE SALVAGED TREES SHALL BE REMOVED WHOLE WITH ROOT WAD ATTACHED AND USED IN RESTORATION CONSTRUCTION AS DIRECTED BY OWNER. TREES FOR REMOVAL WILL BE FLAGGED BY OWNER FOLLOWING STAKING AND PRIOR TO CONSTRUCTION.

LIVE TREES

- ALL TREES NOT MARKED FOR REMOVAL SHALL BE LEFT STANDING UNDISTURBED. CONSTRUCTION ACTIVITY SHALL NOT DEBARK OR DAMAGE LIVE TREES.
- 2. KEEP OUT OF DRIP LINE OF EXISTING TREES TO REMAIN.

CONTRACTOR

- THE CONTRACTOR SHALL SUBMIT THE FOLLOWING PLANS,
 INCLUDING THEIR MEANS AND METHODS OF PERFORMANCE FOR
 THEIR TESC PLAN FOR OWNER REVIEW AND APPROVAL:
- A. TEMPORARY STREAM DIVERSION PLAN FROM TRIBUTARIES AND AROUND RESERVOIR, INCLUDING PUMPING. REMOVAL OF ALL EQUIPMENT AND PIPING FOLLOWING SURFACE WATER DIVERSIONS.
- 3. INITIAL DRAW DOWN PLAN, INCLUDING SILT TURBIDITY CURTAIN, FLOATING INTAKES, SECURING AND MOVING SILT TURBIDITY CURTAIN AND FLOATING INTAKES, PIPING, PUMPING, SPRAYERS AND SPRAYER PLATFORMS AND ALL OTHER METHODS PROPOSED BY CONTRACTOR.
- C. STORM WATER POLLUTION PROTECTION PLAN (SWPPP).
- D. RESERVOIR SEDIMENTS DEWATERING, INCLUDING: PROPOSED METHODS, SITE IMPACTS AND RESTORATION OF SITE IMPACTS REMOVAL OF ALL EQUIPMENT FOLLOWING DEWATERING INCLUDING ANY PROPOSED MODIFICATIONS TO FINAL GRADING.
- E. DAM MATERIAL HANDLING AND DISPOSAL.
- F. PLAN TO PROVIDE TOPSOIL TYPE B FOR NATIVE VEGETATION ESTABLISHMENT IN RESERVOIR AND AREAS USED FOR SEDIMENT DEWATERING.
- G. MEANS AND METHODS DEPICTED IN PLANS ARE CONCEPTUAL IN NATURE. CONTRACTOR MAY PROVIDE ALTERNATIVE DESIGNS WITH EQUAL PERFORMANCE THAT SATISFY REGULATORY REQUIREMENTS, MINIMIZE COST AND ACCELERATE THE SCHEDULE FOR OWNER REVIEW.

FISH SALVAGE AND EXCLUSION PLAN

- 1. THE OWNER SHALL LEAD AND BE RESPONSIBLE FOR FISH SALVAGE. FISH AND FRESH WATER MUSSEL SALVAGE WILL INCLUDE ASSISTANCE FROM WDFW AND CONTRACTOR STAFF. CONTRACTOR TO PROVIDE PUMPS, HOSES AND LABOR TO DEWATER KWONEESUM RESERVOIR, WILDBOY CREEK, AND TRIBUTARIES POOL BY POOL AND PROVIDE TIME AND MATERIALS RATES FOR LABOR ASSISTANCE AND PROVIDE TIME AND MATERIALS RATES PER BID SHEET FOR FISH EXCLUSION ASSISTANCE.
- THE CONTRACTOR SHALL PLAN OPERATIONS TO ANTICIPATE AND ALLOW FOR FISH EXCLUSION AND PROVIDE TWO WEEKS NOTICE TO THE OWNER PRIOR FISH RESCUE OPERATIONS. THE CONTRACTOR SHALL PROVIDE TWO LABORERS, PUMPS, PUMP SCREENS, AND A VEHICLE TO TRANSPORT LABORERS, EQUIPMENT, AND BUCKETS WITH SALVAGED FISH.
- HEN PUMPING IS REQUIRED, THE CONTRACTOR SHALL ISOLATE
 THE WORK AREA(S) WHEN FISH ARE PRESENT, AND PROVIDE A
 PUMP INTAKE FISH SCREEN THAT MEETS NMFS'S FISH SCREEN
 CRITERIA (NMFS 2011, OR MOST CURRENT). WIDER MESH
 SCREENS MAY BE USED AFTER ALL FISH HAVE BEEN REMOVED
 FROM THE ISOLATED AREA. WORK AREA ISOLATION AND FISH
 CAPTURE ACTIVITIES SHALL TAKE PLACE DURING PERIODS OF THE
 COOLEST AIR AND WATER TEMPERATURES POSSIBLE, NORMALLY
 EARLY IN THE MORNING VERSUS LATE IN THE DAY, AND DURING
 CONDITIONS APPROPRIATE TO MINIMIZE STRESS TO FISH SPECIES
 PRESENT.
- 4. DURING INITIAL DRAW DOWN OF THE RESERVOIR, PUMP INTAKES MUST BE SCREENED AS PER REGULATORY REQUIREMENTS. FOR PUMPING OF DIVERTED FLOWS, TRIBUTARY INTAKES MUST BE SCREENED AS PER REGULATORY PERMIT REQUIREMENTS FOR THE


- DURATION OF THE PROJECT. THE CONTRACTOR SHALL SCREEN, AND MAINTAIN TRIBUTARY DIVERSION INLETS WITH SEINE NETS SIZED AS PER REGULATORY PERMIT REQUIREMENTS AND SECURED WITH SANDBAGS OR EQUIVALENTS IF APPROVED BY OWNER.
- 5. FOR TEMPORARY ACCESS ROAD/ROUTE CROSSINGS OF TRIBUTARIES, PRIOR TO CONTRACTOR CONDUCTING ANY IN-WATER WORK, THE OWNER SHALL CONDUCT FISH SALVAGE/RESCUE WITHIN THE PROPOSED IN-WATER WORK AREAS.
- 6. THE OWNER SHALL BE RESPONSIBLE FOR SALVAGING ALL SALVAGEABLE FISH AND FRESHWATER MUSSELS TRAPPED IN RESIDUAL POOLS WITHIN THE PROJECT AREA. THEY WILL BE CAREFULLY COLLECTED BY SEINE AND/OR DIP NETS AND PLACED IN CLEAN TRANSFER CONTAINERS WITH ADEQUATE VOLUMES OF FRESH RIVER WATER.
- ALL FISH AND FRESHWATER MUSSELS TRAPPED IN RESIDUAL POOLS WITHIN THE PROJECT AREA WILL BE CAREFULLY COLLECTED BY SEINE AND/OR DIP NETS AND PLACED IN CLEAN TRANSFER CONTAINERS WITH ADEQUATE VOLUME OF FRESH RIVER WATER.
- FISH SHALL BE EXCLUDED FROM THE WORK AREA WITH SEINE NET OR OTHER METHOD APPROVED BY WDFW AND OWNER PERSONNEL.


RESERVOIR

- FISH SALVAGE IN THE RESERVOIR SHALL OCCUR AFTER THE INITIAL DRAW DOWN OF THE RESERVOIR TO CONCENTRATE FISH IN A REDUCED AREA.
- 2. WDFW WILL ASSIST THE FISH SALVAGE/RESCUE EFFORT WITH THEIR ELECTRO-FISHING BOAT. THE CONTRACTOR SHALL ASSIST WDFW STAFF IN LAUNCHING AND TRAILERING THEIR ELECTRO-FISHING BOAT DUE TO POTENTIAL ACCESS CONSTRAINTS DUE TO WATER LEVELS/DRAW DOWN CONDITIONS. ELECTRO-FISHING SHALL CONTINUE UNTIL WDFW OR OWNER CONFIRM ALL SALVAGEABLE FISH HAVE BEEN SALVAGED.

WILDBOY CREEK

1. THE CONTRACTOR SHALL PERFORM FISH EXCLUSION IN WILDBOY CREEK WITH ASSISTANCE FROM THE COWLITZ INDIAN TRIBE FISHERIES BIOLOGIST. FISH SALVAGE SHALL INCLUDE THE CONTRACTOR PROVIDING SCREENED INTAKE PUMPS AND OPERATING THE PUMPS TO CONCENTRATE FISH IN POOLS. THE POOLS SHALL BE PUMPED DOWN TO ALLOW FOR SYSTEMATIC SFINE NETTING THROUGH THE WORK AREAS. FOLLOWING SEINE NETTING, THE WORK AREAS WILL BE ISOLATED TO EXCLUDE FISH WITH SEINE NETS THAT MUST BE KEPT CLEAN OF DEBRIS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR SKIMMING DEBRIS OFF SEINE NETS THROUGHOUT CONSTRUCTION. AFTER OWNER COMPLETES FISH SALVAGE/RESCUE, THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING APPROPRIATELY SIZED SEINES OR EQUIVALENTS FOR FISH EXCLUSION FOR THE DURATION OF THE PROJECT. CONTRACTOR SHALL ALSO MAINTAIN FISH EXCLUSION MEASURES (SEINES OR EQUIVALENTS) FOR THE DURATION OF THE PROJECT.









STE: KWONEESUM DAM
REMOVAL DESIGN

TITLE:

GENERAL NOTES

SCALE: DATE: DRAWN: CHECKED: BN
11/17/23 RP BN

TEMPORARY EROSION SEDIMENTATION CONTROL (TESC) PLAN

- 1. THE TEMPORARY EROSION AND SEDIMENT CONTROL (TESC) MEASURES DEPICTED IN THESE DRAWINGS IS FOR INFORMATIONAL PURPOSES ONLY. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR PROVIDING EROSION CONTROL MEASURES TO COMPLY WITH APPLICABLE REGULATIONS.
- THE TESC PLAN MEASURES DEPICTED IN THESE DRAWINGS WILL PROVIDE A
 GUIDELINE FOR THE CONTRACTOR TO DEVELOP AND IMPLEMENT AN TESC PLAN.
- 3. THE IMPLEMENTATION OF AN TESC PLAN AND THE CONSTRUCTION, MAINTENANCE, REPLACEMENT, AND UPGRADING OF THESE TESC FACILITIES IS THE RESPONSIBILITY OF THE CONTRACTOR UNTIL ALL CONSTRUCTION IS COMPLETED AND APPROVED AND VEGETATION/LANDSCAPING IS ESTABLISHED.
- 4. THE BOUNDARIES OF THE CLEARING LIMITS SHOWN ON THIS PLAN SHALL BE CLEARLY FLAGGED IN THE FIELD PRIOR TO CONSTRUCTION. DURING THE CONSTRUCTION PERIOD, NO DISTURBANCE BEYOND THE FLAGGED CLEARING LIMITS SHALL BE PERMITTED. THE FLAGGING SHALL BE MAINTAINED BY THE CONTRACTOR FOR THE DURATION OF CONSTRUCTION.
- 5. THE CONTRACTOR'S TESC FACILITIES ARE TO BE CONSTRUCTED PRIOR TO CLEARING AND GRADING ACTIVITIES, AND IN SUCH A MANNER AS TO ENSURE THAT SEDIMENT AND SEDIMENT-LADEN WATER DO NOT ENTER SURFACE WATERS, THE DRAINAGE SYSTEM, OR VIOLATE APPLICABLE WATER STANDARDS.
- 6. THE TESC MEASURES DEPICTED IN THESE DRAWINGS ARE THE MINIMUM REQUIREMENTS FOR ANTICIPATED SITE CONDITIONS. DURING THE CONSTRUCTION PERIOD, THE CONTRACTOR'S TESC FACILITIES SHALL BE UPGRADED AS NEEDED AT NO ADDITIONAL COST FOR UNEXPECTED STORM EVENTS AND TO ENSURE THAT SEDIMENT AND SEDIMENT-LADEN WATER DO NOT LEAVE THE SITE.
- 7. THE TESC FACILITIES SHALL BE INSPECTED DAILY BY THE CONTRACTOR AND MAINTAINED AS NECESSARY TO ENSURE THEIR CONTINUED FUNCTIONING.
- 8. THE CONTRACTOR'STESC FACILITIES ON INACTIVE SITES SHALL BE INSPECTED AND MAINTAINED A MINIMUM OF ONCE A MONTH OR WITHIN THE 24 HOURS FOLLOWING A STORM EVENT.
- STABILIZED CONSTRUCTION ENTRANCES AND ADDITIONAL MEASURES MAY BE REQUIRED AND SHALL BE MAINTAINED FOR THE DURATION OF THE PROJECT TO ENSURE ALL ACCESS ROADS ARE KEPT CLEAN, MAINTAINED THROUGHOUT CONSTRUCTION, AND LEFT AT CONTRACTOR DEMOBILIZATION IN EQUAL OR BETTER CONDITION AT NO ADDITIONAL COST.

INSPECTION AND MAINTENANCE

1. ALL TESC FACILITIES SHALL BE INSPECTED, MAINTAINED, AND REPAIRED AS NEEDED TO ASSURE CONTINUED PERFORMANCE OF THEIR INTENDED FUNCTION. ALL TESC FACILITIES SHALL BE INSPECTED WEEKLY AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5 INCHES OF RAIN PER 24 HOUR PERIOD AND AFTER EVENTS EXCEEDING 2 HOURS DURATION. TURBIDITY MONITORING SHALL OCCUR AS PER ALL PERMIT REQUIREMENTS.

CONTRACTOR'S TESC RECORD

- 1. WEEKLY REPORTS SUMMARIZING THE SCOPE OF INSPECTIONS, THE PERSONNEL CONDUCTING THE INSPECTION, THE DATE(S) OF THE INSPECTION, MAJOR OBSERVATIONS RELATING TO THE IMPLEMENTATION OF THE CONTRACTOR'S EROSION AND SEDIMENT CONTROL PLAN, AND ACTIONS TAKEN AS A RESULT OF THESE INSPECTIONS SHALL BE PREPARED AND RETAINED ON SITE BY THE CONTRACTOR. IN ADDITION, A RECORD OF THE FOLLOWING DATES SHALL BE INCLUDED IN THE REPORTS:
- A. WHEN MAJOR GRADING ACTIVITIES OCCUR.
- B. DATES OF RAINFALL EVENTS EITHER EXCEEDING 2 HOURS DURATION OR MORE THAN 0.5 INCHES/24 HOURS.
- C. WHEN CONSTRUCTION ACTIVITIES TEMPORARILY OR PERMANENTLY CEASE ON SITE, OR ON A PORTION OF THE SITE.
- D. WHEN STABILIZATION MEASURES ARE INITIATED FOR PORTIONS OF THE SITE.
- E. TESC RECORDS SHALL BE MADE AVAILABLE TO THE OWNER ON REQUEST AND SHALL BE PROVIDED FOR REVIEW AND APPROVAL PRIOR TO APPLICATION FOR

PAYMENT.

STABILIZE SOILS AND PROTECT SLOPES

- 1. FROM MAY 1 THROUGH SEPTEMBER 30, ALL EXPOSED SOILS SHALL BE PROTECTED FROM EROSION BY MULCHING, HYDROSEED COVERING, OR OTHER APPROVED MEASURES WITHIN SEVEN DAYS OF GRADING. FROM OCTOBER 1 THROUGH APRIL 30, ALL EXPOSED SOILS MUST BE PROTECTED WITHIN 2 DAYS OF GRADING. SOILS SHALL BE STABILIZED BEFORE A WORK SHUTDOWN, HOLIDAY OR WEEKEND IF NEEDED BASED ON THE WEATHER FORECAST. SOIL STOCK PILINGS MUST BE STABILIZED AND PROTECTED WITH SEDIMENT TRAPPING MEASURES. MULCH AS SOON AS PRACTICAL ALL DISTURBED AREAS NOT INDICATED IN THE CONTRACT DOCUMENTS FOR OTHER PERMANENT STABILIZATION. MEASURES. HAY, STRAW, AND MULCH USED ON SITE SHALL BE 99.9% WEED FREE. CONTRACTOR SHALL CONDUCT INTERIM SEEDING WITH REGREEN OR OWNER-APPROVED EQUIVALENT TO STABILIZE SOILS AND PROTECT SLOPES WHERE NEEDED TO AVOID SEDIMENT DELIVERY TO PROJECT WATERS PRIOR TO PERMANENT SEEDING AND SITE RESTORATION EFFORTS.
- 2. DESIGN, CONSTRUCT, AND PHASE CUT AND FILL SLOPES IN A MANNER THAT WILL MINIMIZE EROSION. REDUCE SLOPE VELOCITIES ON DISTURBED SLOPES BY PROVIDING TEMPORARY BARRIERS. STORMWATER FROM OFF SITE SHOULD BE HANDLED SEPARATELY FROM STORMWATER GENERATED ON SITE.


AFTER FINAL SITE STABILIZATION

1. ALL TEMPORARY EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER FINAL SITE STABILIZATION IS ACHIEVED OR AFTER THE TEMPORARY BEST MANAGEMENT PRACTICES (BMPS) ARE NO LONGER NEEDED. TRAPPED SEDIMENT SHALL BE REMOVED FROM THE SITE OR INCORPORATED INTO FINISHED GRADING. DISTURBED SOIL AREAS RESULTING FROM REMOVAL SHALL BE PERMANENTLY STABILIZED UNLESS OTHERWISE DIRECTED BY THE OWNER IN WRITING.

CONSTRUCTION DEWATERING

1. CONTRACTOR SHALL PERFORM CONSTRUCTION DEWATERING IN SUCH A MANNER AS TO AVOID THE RELEASE OF SEDIMENT-LADEN WATER TO SURFACE WATERS. SEDIMENT LADEN WATER MAY BE PUMPED TO AN UPLAND DISCHARGE LOCATION AND ALLOWED TO INFILTRATE INTO THE GROUND. IF SURFACE RUNNOFF IS OCCURING AS A RESULT OF DEWATERING OPERATIONS, THE CONTRACTOR MAY BE REQUIRED TO THROTTLE DOWN PUMPS AND PROVIDE ADDITIONAL EROSION CONTROL MEASURES AS NECESSARY TO COMPLY WITH LAWS AND PERMIT REQUIREMENTS AT NO ADDITIONAL COST TO THE OWNER.

ABBREV	/IATIONS	AL.	ALUMINUM
APPROX	APPROXIMATE	BST	BITUMINOUS SURFACE TREATMENT
AV	AIR VOIDS	CL.	CLASS
BMP	BEST MANAGEMENT PRACTICES	CFM	CUBIC FEET PER MINUTE
CMP	CORRUGATED METAL PIPE	CFS	CUBIC FEET PER SECOND
DBH	DIAMETER BREAST HEIGHT	COMB.	COMBINATION
EA	EACH	CONC.	CONCRETE
ELEV	ELEVATION		
GIS	GEOGRAPHICAL INFORMATION SYSTEM	CPA	COMPACTION PRICE ADJUSTMENT
HORIZ	HORIZONTAL	CPF	COMPOSITE PAY FACTOR
INV	INVERT	CRIB.	CRIBBING
LWM	LARGE WOODY MATERIAL	CULV.	CULVERT
MAX	MAXIMUM	CY OR CU Y	D. CUBIC YARD
MIN	MINIMUM	DIAM.	DIAMETER
NMFS	NATIONAL MARINE FISHERIES	EST.	ESTIMATE OR ESTIMATED
WIVII 5	SERVICE	EXCL.	EXCLUDING
OHW	ORDINARY HIGH WATER	F	FAHRENHEIT
%	PERCENT	GPH	GALLON PER HOUR
RM	RIVER MILE	GPM	GALLON PER MINUTE
RTK	REAL TIME KINEMATICS	HUND.	HUNDRED
SFM	STRUCTURE FROM MOTION	НМА	HOT MIX ASPHALT
		IN.	INCH
STA	STATION TENANCIPARY ENGLISH AND	INCL.	INCLUDING
TESC	TEMPORARY EROSION AND SEDIMENT CONTROL	JMCAF	JOB MIX COMPLIANCE PRICE ADJUSTMENT
TBD	TO BE DETERMINED	JMF	JOB MIX FORMULA
TYP	TYPICAL	LB	POUND(S)
DOE	WASHINGTON STATE DEPARTMENT OF ECOLOGY	LF OR LIN. F	,
EPA	ENVIRONMENTAL PROTECTION	LS	LUMP SUM
EPA	AGENCY	M	THOUSAND
FOP	FIELD OPERATING PROCEDURE	MBM	THOUSAND FEET BOARD MEASURE
		MUTS STRENGTH	MINIMUM ULTIMATE TENSILE
NEPA	NATIONAL ENVIRONMENTAL POLICY ACT	PCPS	PRECAST PRESTRESSED
NEDA		PRES.	PRESSURE
NFPA	NATIONAL FIRE PROTECTION ASSOCIATION	PSF	POUNDS PER SQUARE FOOT
NIST	NATIONAL INSTITUTE OF	PSI	POUNDS PER SQUARE INCH
11131	STANDARDS AND TECHNOLOGY	PVC	POLYVINYL CHLORIDE
QPL	QUALIFIED PRODUCTS LIST	RAP	RECYCLED ASPHALT PAVEMENT
RAM	REQUEST FOR APPROVAL OF	REG.	REGULATOR
	MATERIAL	REINF.	REINFORCED, REINFORCING
RCW	REVISED CODE OF WASHINGTON	SEC.	SECTION
	(LAWS OF THE STATE)	ST.	STEEL
SEPA	STATE ENVIRONMENTAL POLICY ACT	STR. SY OR SQ. Y	STRUCTURAL 'D. SQUARE YARD(S)
SOP	STANDARD OPERATING PROCEDURE	TH.	THICK OR THICKNESS
WAC	WASHINGTON ADMINISTRATIVE CODE	TR. VFA	TREATMENT VOIDS FILLED WITH ASPHALT
WDFW	WASHINGTON DEPARTMENT OF FISH AND WILDLIFE	VMA VERT WSE	VOIDS IN MINERAL AGGREGATE VERTICAL WATER SURFACE ELEVATION
WISHA	WASHINGTON INDUSTRIAL SAFETY AND HEALTH ADMINISTRATION	YR	YEAR
WSDOT	WASHINGTON STATE DEPARTMENT OF TRANSPORTATION		
AGG.	AGGREGATE		



3	-	-	-
2	-	-	-
1	-	-	1
REV:	DESCRIPTION:	BY:	DATE:
STATUS	*FINAL DESIGN		







STTE: KWONEESUM DAM
REMOVAL DESIGN


TITLE:

GENERAL NOTES


SCALE: DATE: DRAWN: CHECKED:
11/17/23 RP BN







LEGEND



(OFF ROAD)

PROPOSED TEMPORARY ACCESS ROADS
(WILDBOY CREEK)

WATER TURBIDITY MONITORS

PROPOSED TEMPORARY ACCESS ROADS

PROPOSED ROCK CONTAINMENT (TO REMAIN, EXCLUDING BREACH FOR EAST TRIBUTARY)

PROJECT BOUNDARY AREA


PROPOSED TRIBUTARIES

——— EPHEMERAL TRIBUTARY


__ _ _ LIMITS OF DISTURBANCE

STAGING AND STOCKPILE

Notes:



SHEET LOCATION



3	-	-	-
2	-		-
1	-	-	-
REV:	DESCRIPTION:	BY:	DATE:







KWONEESUM DAM REMOVAL DESIGN

TITLE:

PROJECT INDEX MAP

SCALE:	DATE:	DRAWN:	CHECKED:
	11/17/23	RP	BN
PROJ. NO:	DRAWING NO:		Total Sheets:
-		5	74






POTENTIAL CONSTRUCTION SEQUENCE

- STEP 1 IN THIS SEQUENCE HAS BEEN PERFORMED UNDER A SEPARATE CONTRACT PRIOR TO THE DAM REMOVAL CONTRACT. SEPARATE PILES OF BOULDERS, COBBLE, GRAVEL AND SOIL ARE LOCATED IN THE STAGING AND STOCKPILE AREA LOCATED SOUTHEAST OF THE RESERVOIR.
- CLEAR AND GRUB SELECTED STAGING AREAS, ACCESS ROADS, INCLUDING ACCESS AROUND THE RESERVOIR TO TRIBUTARY DIVERSION LOCATIONS, TEXAS CREEK DISCHARGE LOCATIONS, AND WILDBOY CREEK ACCESS LOCATIONS DOWNSTREAM OF DAM.
- INSTALL TEMPORARY STREAM DIVERSION PIPING FROM TRIBUTARY DIVERSION LOCATIONS TO TEXAS CREEK.
- 4. INSTALL TRIBUTARY DIVERSION DAMS COORDINATE WITH OWNER TO ALLOW FOR FISH SALVAGE/RESCUE PRIOR TO INSTALLING TRIBUTARY DIVERSION DAMS. PLACE SCREENED INTAKES, PUMP, AND SPILL CONTAINMENT MEASURES. PLACE OUTLET EROSION CONTROL MEASURES IN TEXAS CREEK PRIOR TO INITIATING TEMPORARY STREAM DIVERSION.
- 5. AN EXPERIENCED BIOLOGIST WILL LEAD A TEAM THAT BEGINS CLEARING FISH 3-5 DAYS PRIOR TO DIVERTING TRIBUTARY FLOWS. THE OWNER EXPECTS TO HAVE MULTIPLE ELECTRO-FISHING CREWS AND WDFW VOLUNTEERS TO CLEAR THE 0.25 MILE REACH DOWNSTREAM OF THE DAM. AN INITIAL FISH RESCUE PASS WILL BE PERFORMED IN THE 0.25 MILE LONG REACH DOWNSTREAM OF THE DAM TO THE EXISTING SPRING LOCATED NEAR THE LEFT BANK OR WILDBOY CREEK. FISH CLEARING WILL OCCUR IN DEFINED SECTIONS/SUB REACHES BY USING SEINES AS BLOCK NETS.
- 6. DIVERT TRIBUTARY FLOWS EARLY IN THE MORNING TO CONCENTRATE REMAINING FISH IN RESIDUAL POOLS IN THE 0.25 MILE REACH DOWNSTREAM OF THE DAM. SIMULTANEOUSLY, BEGIN THE SECOND ROUND OF FISH CLEARING AS THE 0.25 MILE REACH DOWNSTREAM OF THE DAM BEGINS TO DEWATER. THE CONTRACTOR SHALL ASSIST BY PUMPING DOWN EACH RESIDUAL POOL WITH A NMFS APPROVED SCREENED INTAKE WHILE FISH RESCUE IS PERFORMED IN EACH REMAINING POOL. THE OWNER EXPECTS TO HAVE MULTIPLE ELECTRO-FISHING CREWS TO CLEAR THE 0.25 MILE REACH DOWNSTREAM OF THE DAM. THE SECOND PASS OF FISH CLEARING IS EXPECTED TO TAKE AN ADDITIONAL 2-4 DAYS TO FULLY CLEAR FISH FROM THE 0.25 REACH DOWNSTREAM OF THE DAM.
- 7. INSTALL A SANDBAG DAM TO FORM A SPRING COLLECTION POOL DOWNSTREAM OF THE SPRING AND INSTALL A GRAVITY PIPELINE ALONG THE BANK OF WILDBOY CREEK TO CONVEY WATER TO DOWNSTREAM OF THE CONFLUENCE WITH TEXAS CREEK. THIS IS THE EXAMPLE FOR PROVIDING COLLECTION AND CONVEYANCE FOR ONE SPRING. THE CONTRACTOR SHALL INCLUDE COLLECTION AND CONVEYANCE OF 3 SPRINGS IN THEIR BID FOR TEMPORARY STREAM DIVERSION. CONTRACTOR MAY PROPOSE ALTERNATIVE METHODS/METHODS OF DIVERTING SPRING FLOWS (E.G., GRAVITY/PUMPING/HDPE/LAYFLAT/ETC) IN TEMPORARY STREAM DIVERSION PLAN(S).
- S. AFTER FISH ARE CLEARED FROM THE 0.25 MILE REACH DOWNSTREAM OF THE DAM, BEGIN CLEARING FISH FROM THE 0.25 MILE REACH FROM THE EXISTING SPRING TO THE CONFLUENCE WITH TEXAS CREEK. THE FIRST PASS OF FISH CLEARING WILL OCCUR IN THIS REACH WHILE THE SPRING IS STILL FLOWING TO THE CONFLUENCE WITH TEXAS CREEK. FISH CLEARING WILL OCCUR IN DEFINED SECTIONS/SUB REACHES BY USING SEINES AS BLOCK NETS. THE OWNER EXPECTS TO HAVE MULTIPLE ELECTRO-FISHING CREWS AND WDFW VOLUNTEERS TO CLEAR THE 0.25 MILE REACH TO TEXAS CREEK. THE FISH CLEARING IS EXPECTED TO TAKE AN ADDITIONAL 3-5 DAYS TO FULLY CLEAR FISH FROM THE 0.25 REACH TO THE CONFLUENCE WITH TEXAS CREEK.
- 9. PLACE SILT CURTAIN IN RESERVOIR. PLACE FLOATING INTAKES, PUMPS AND DEWATERING SPRAYERS TO PREPARE FOR INITIAL DRAWDOWN. PLACE CLEARWATER PUMP ON THE DAM FACE TO PREPARE FOR INITIAL DRAWDOWN. THE FLOATING INTAKES ARE INTENDED TO INTERCEPT TURBID WATER GENERATED ALONG SHORELINES DURING INITIAL DRAWDOWN. FLOWS PUMPED FROM THE FLOATING INTAKES WILL BE CONVEYED TO DEWATERING SPRAYERS FOR LAND APPLICATION AND INFILTRATION.
- 10. COMMENCE CLEARWATER DIVERSION PUMPING, AND FLOATING INTAKE PUMPING. THE MAXIMUM DRAWDOWN IN RESERVOIR WSE SHALL BE NO GREATER THAN 2 FEET PER 24 HOURS, UNLESS OTHERWISE APPROVED BY THE OWNER. APPROVAL OF INCREASED RESERVOIR WSE DRAWDOWN WILL REQUIRE AUTHORIZATION FROM

- DOE DAM SAFETY AND CONTRACTOR'S SUCCESSFUL DEMONSTRATION OF MEETING TURBIDITY MONITORING AND DISCHARGE REQUIREMENTS. THE 2 FEET PER DAY DRAWDOWN OF RESERVOIR WSE MAY BE REDUCED IF CONTRACTOR DOES NOT SUCCESSFULLY DEMONSTRATE MEETING TURBIDITY MONITORING AND DISCHARGE REQUIREMENTS. THE CONTRACTOR SHALL MONITOR SPRAY LOCATIONS (IF USED) IN THE DEWATERING/PROCESSING AREA AND THROTTLE DOWN PUMPED FLOWS TO AVOID SURFACE RUNOFF. THE CLEARWATER PUMP WILL PUMP WATER FROM DEEPER PORTIONS OF THE RESERVOIR OVER THE DAM, WHILE ASSURING THE CLEARWATER PUMP'S INTAKE IS SUFFICIENTLY ABOVE FINE SEDIMENTS LOCATED AT THE BOTTOM OF THE RESERVOIR TO AVOID MOBILIZING THOSE SEDIMENTS. FLOATING INTAKE PUMPS WILL OPERATE AT A SLIGHTLY HIGHER CUMULATIVE FLOW RATE THAN THE CLEARWATER PUMP TO AVOID TURBID WATER FROM PASSING UNDER THE SILT CURTAIN. CONTRACTOR MUST MONITOR PUMPING RATES AND TURBIDITY PLUMES TO AVOID SEDIMENT TRANSPORTED TO INSIDE OF SILT CURTAIN.
- 11. MONITOR TURBIDITY PLUMES IN THE ISOLATED RESERVOIR AND ADJUST LINES SECURING TURBIDITY CURTAIN AND FLOATING INTAKES AS RESERVOIR LEVELS DESCEND. ADJUST LOCATION OF TURBIDITY CURTAIN AND FLOATING INTAKES, AS NECESSARY TO AVOID DISTURBING RESERVOIR SEDIMENTS. CONTINUE TO MONITOR TURBIDITY LEVELS DURING INITIAL DRAWDOWN. INITIAL DRAWDOWN OF MORE THAN 10 FEET WILL SIGNIFICANTLY REDUCE IMPOUNDED SEDIMENTS DEWATERING DURATION. CONTRACTOR MAY PUMP 24 HOURS PER DAY, PENDING APPROVAL OF WATER QUALITY MONITORING PLAN, ADEQUATE MONITORING AND MAINTAINING PERMIT COMPLIANCE.
- 12. PARTIALLY DEMOLISH CONCRETE DAM FACE WHILE RETAINING DEMOLITION DEBRIS AND CREATE A LEVEL PLATFORM TO MOVE CLEARWATER PUMP DOWN DAM FACE TO REDUCE SUCTION HEAD AS NECESSARY AS RESERVOIR LEVELS DESCEND. CONTINUE TO MONITOR TURBIDITY LEVELS IN THE RESERVOIR DURING INITIAL DRAWN DOWN. CONTRACTOR SHALL ASSIST WDFW IN DEPLOYING AND RETRIEVING ELECTROFISHING BOAT.
- 13. AFTER CLEARWATER PUMPING HAS CEASED, REMOVE THE SILT CURTAIN AND PERFORM FISH RESCUE WITHIN THE RESERVOIR. FLOATING INTAKES SHALL REMAIN IN THE RESERVOIR DURING FISH RESCUE. REMOVE CLEARWATER PUMP.
- 14. THE CONTRACTOR SHALL RELOCATE FLOATING INTAKES TO DEEPER PORTIONS OF THE RESERVOIR AND CONTINUE TO PUMP TO THE DEWATERING/PROCESSING AREA AS LONG AS FLOATING INTAKES ARE 2-FEET, MINIMUM, ABOVE FINE SEDIMENTS LOCATED AT THE BOTTOM OF THE RESERVOIR. CLEAR AND GRUB FOR IMPOUNDED SEDIMENTS DEWATERING AS NECESSARY.
- 15. LARGE WOOD STRUCTURES IN WILDBOY CREEK (SHEETS 52-66)
 DOWNSTREAM OF KWONEESUM DAM MAY BE CONSTRUCTED
 CONCURRENTLY WITH STEPS 15-20 OF THIS POTENTIAL
 CONSTRUCTION SEQUENCE PROVIDED FISH AND FRESHWATER
 MUSSEL SALVAGE/RESCUE HAS BEEN COMPLETED AND SUFFICIENT
 MATERIAL IS AVAILABLE.
- 16. DAM DEMOLITION CAN COMMENCE FROM THE TOP DOWN AS LONG AS 5 FEET OF FREEBOARD IS MAINTAINED. REMOVE AND PROPERLY DISPOSE OF CONCRETE (INCLUDING REBAR) OFFSITE ACCORDING TO SPECIFICATIONS. RELOCATE PUMPS AND CONTAINMENT IF ALLOWABLE SUCTION HEAD IS EXCEEDED.
- 17. PERFORM DEWATERING OF THE RESERVOIR SEDIMENTS, CONTRACTOR MAY USE A COMBINATION OF DEWATERING METHODS FOR RESERVOIR SEDIMENTS. THE DEWATERING/PROCESSING AREA SHOWN ON SHEETS 6 AND 13 MAY BE USED PROVIDING THE CONTRACTOR MEETS ALL PERMIT REQUIREMENTS FOR CONTAINMENT OF SEDIMENTS. THE DEWATERING/PROCESSING AREA MAY BE CLEARED AND RE-CONTOURED FOR DEWATERING PURPOSES AS LONG AS THE GROUND SURFACE IN THE DEWATERING/PROCESSING AREA IS RESTORED TO PRE CONSTRUCTION CONTOURS AND FREELY DRAINS, EXISTING VEGETATION IS SALVAGED AS SLASH, A NATIVE VEGETATION ESTABLISHMENT GROWING MEDIUM IS PROVIDED IN THE DEWATERING/PROCESSING AREA AND THE RESERVOIR, AND THE DEWATERING/PROCESSING AREA IS PLANTED WITH NATIVE VEGETATION WITH SPECIES AND DENSITY SIMILAR TO EXISTING CONDITIONS. SEE SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS FOR RESTORATION OF ALTERNATIVE DEWATERING/PROCESSING

AREAS.

- 18. CONTINUE DAM DEMOLITION WHILE MAINTAINING 5 FEET, MINIMUM FREEBOARD UNTIL FINE SEDIMENT HAVE BEEN RELOCATED.
- 19. INSTALL DEWATERING COFFERDAM 1 UPSTREAM OF DAM AND PUMP WATER DOWNSTREAM OF THE DAM PRIOR TO REMOVING BOTTOM 10 FEET OF CONCRETE APRON AT THE UPSTREAM FACE OF DAM, SHEET 26. AFTER FINE SEDIMENT HAS BEEN RELOCATED TO CONFINED AREAS OF THE FORMER RESERVOIR AND ALLOWED TO DRAIN, MIX WITH SOIL SALVAGED AND STOCKPILE ONSITE AS REFERENCED IN STEP 1 OF THIS SEQUENCE. THE DRAINED AND MIXED SOILS SHALL BE SPREAD IN UNCONFINED AREAS OF THE RESERVOIR, OUTSIDE OF STREAM CHANNEL ALIGNMENTS.
- 20. SALVAGE AND STOCKPILE DELTAIC SEDIMENTS (SAND AND GRAVEL) FOR CHANNEL CONSTRUCTION. STAGE AND STOCKPILE ROCK SALVAGED FROM DAM AND SPILLWAY DEMOLITION THAT WILL BE USED FOR LARGE WOOD STRUCTURE CONSTRUCTION AND OTHER PURPOSES.
- 21. USE DEWATERING COFFERDAM 1 TO COMPLETELY REMOVE DAM AND CONSTRUCT WILDBOY CREEK CHANNEL WITHIN FORMER DAM FOOTPRINT. USE THE PLUNGE POOL (DOWNSTREAM OF THE FORMER DAM) AS A SEDIMENT TRAP AFTER CHANNEL IS CONSTRUCTED WITHIN FORMER DAM FOOTPRINT. TURBID WATER COLLECTED IN THE PLUNGE POOL SHALL BE PUMPED TO UPLAND INFILTRATION AREA. ALTERNATE USE OF DEWATERING COFFERDAM 1 AND PLUNGE POOL DEWATERING, AS NECESSARY TO CONSTRUCT TRIBUTARY CHANNELS WITHIN THE RESERVOIR.
- 22. AFTER CHANNELS HAVE BEEN CONSTRUCTED WITHIN THE RESERVOIR, REINTRODUCE TRIBUTARY FLOWS, ONE AT A TIME TO FLUSH SEDIMENT FROM EACH CONSTRUCTED TRIBUTARY CHANNEL. THE ABILITY TO PUMP FROM EACH TRIBUTARY DIVERSION SHALL REMAIN INTACT UNTIL ALL CHANNELS HAVE BEEN FLUSHED, ONE AT A TIME. INITIAL FLUSHING OF TRIBUTARY CHANNELS SHALL BE COLLECTED IN THE PLUNGE POOL DOWNSTREAM OF THE FORMER DAM LOCATION AND PUMPED TO UPLAND FILTRATION AREA. AFTER ALL TRIBUTARIES HAVE BEEN FLUSHED ONE AT A TIME, SUBSEQUENTLY REMOVE TRIBUTARY DIVERSION DAM AND PIPING FOR EACH TRIBUTARY AND ALLOW FLOW THROUGH THE PROJECT.
- 23. CONTRACTOR SHALL FULLY DECOMMISSION AND RESTORE ALL TEMPORARILY DISTURBED AREAS PER THE SPECIFICATIONS.
- 24. PERFORM FINAL SITE STABILIZATION AND PERMANENT ACCESS ROAD REPAIRS PER BID SHEET AND SPECIFICATIONS.
- 25. PERFORM FINAL SITE STABILIZATION.



	. – – .		
3	-	-	-
2	-		-
1	=		-
REV:	DESCRIPTION:	BY:	DATE:
STATU	* FINAL DESIGN		







KWONEESUM DAM REMOVAL DESIGN


TITLE:


CONSTRUCTION SEQUENCE NOTES


SCALE:	DATE:	DRAWN:	CHECKED:
	11/17/23	RP	BN
PROJ. NO:	DRAWING NO:	_	Total Sheets:
-		8	74


















TYPICAL SECTION - PUMPING INLET HEADER



TYPICAL SECTION - PUMPING OUTLET FLANGE NOT TO SCALE

BY: DATE: REV: DESCRIPTION: STATUS: FINAL DESIGN





KWONEESUM DAM REMOVAL DESIGN


KWONEESUM RESERVOIR & DAM - DEWATERING TYPICAL DETAILS


11/17/23 RP BN 14


NOTE: CONTRACTOR MAY PROVIDE ALTERNATE DESIGN WITH EQUAL PERFORMANCE.


TYPICAL DETAIL - TEMPORARY PUMPING HEADER


NOT TO SCALE












NOT TO SCALE





STATUS: FINAL DESIGN





KWONEESUM DAM REMOVAL DESIGN

REMOVAL DESIGN


KWONEESUM RESERVOIR & DAM - DEWATERING TYPICAL DETAILS

SCALE:	DATE:	DRAWN:	CHECKED:
	11/17/23	RP	BN
PROJ. NO:	DRAWING NO:		Total Sheets:
_		19	74






DETAIL - FLANGE ADAPTER AND BACK-UP RING



DETAIL - BOLT LENGTH PARAMETERS


IPS PIPE	FLANGE	BOLT PIPF	BOLT HOLE	NO. OF
SIZE	OD	DIAMEER	DIAMETER	BOLTS
SIZE		DIAIVIEER	DIAIVIETER	BUL13
6	11.00	9.50	0.88	8
8	13.50	11.75	0.88	8
18	25.00	22.75	1.25	16
24	32.00	29.50	1.38	20

TABLE - FLANGE DIMENSIONS (INCH SIZED) ANSI B16.5 CLASS 150




FULL FACE STYLE

DETAIL - FLANGE GASKET STYLES



DETAIL - FLANGE BOLT TIGHTENING PATTERNS



DETAIL - FLANGE CONNECTION TO SPRAYER PLATFORM







302 W. Steuben St. #6



	DL17 (1L				
SCALE:	DATE:	DRAWN:	CHECKED:		
	11/17/23	RP	BN		
PROJ. NO:	DRAWING NO:		Total Sheets:		
-		20	74		

TYPICAL DETAIL - FLANGE ADAPTER AND BACKUP RING
NOT TO SCALE







FULL FLAT

TYPICAL DETAIL - PRECAST CONCRETE BLOCK

NOT TO SCALE





3	-	1	
2	-	-	-
1	-	1	
REV:	DESCRIPTION:	BY:	DATE:
STATU	FINAL DESIGN		








KWONEESUM DAM REMOVAL DESIGN

TITLE KWONEESUM RESERVOIR &
DAM - SEDIMENT
MANAGEMENT TYPICAL
DETAIL


SCALE:	DATE:	DRAWN:	CHECKED:
	11/17/23	RP	BN
PROJ. NO:	DRAWING NO:		Total Sheets:
-		21	74








CROSS-SECTION - NORTH TRIBUTARY



CROSS-SECTION - WEST TRIBUTARY



24

3 CROSS-SECTION - EAST TRIBUTARY

LEGEND


- · - · · - SONAR RETURN SURFACE GRADE


ORDINARY HIGH WATER (OHW)

PROPOSED GRADE

NOTES:
CONTRACTOR SHALL ANTICIPATE AND
ASSUME FIT-IN-THE-FIELD APPROACH
TO CUTS AND FILLS WITHIN THE
RESERVOIR FOOTPRINT BASED ON
EXPOSED SURFACES AFTER RESERVOIR
DRAWDOWN AND HABITAT GOALS.

ALL CROSS-SECTIONS ARE ORIENTED LEFT TO RIGHT LOOKING DOWNSTREAM.





3	-	-	-
2	-	-	-
1	-	-	-
REV:	DESCRIPTION:	BY:	DATE:
	DESCRIPTION: S: FINAL DESIGN	BY:	DATE:






KWONEESUM DAM REMOVAL DESIGN


KWONEESUM RESERVOIR &
DAM – MASS GRADING
CROSS-SECTIONS

SCALE:	DATE:	DRAWN:	CHECKED:
	11/17/23	RP	BN
PROJ. NO:	DRAWING NO:		Total Sheets:
	1 24		1 7/



TYPICAL SECTION VIEW: SINGLE LAYER

NOT TO SCALE




TYPICAL SECTION VIEW: STACKED LAYERS

COFFERDAM NOTES:

- 1. BULKBAG COFFERDAM IS A PRE-APPROVED METHOD FOR ISOLATING THE WORK AREA FROM SURFACE FLOWS. CONTRACTOR MAY SUBMIT ALTERNATE COFFERDAM DESIGN TO THE OWNER FOR REVIEW AND APPROVAL. ALTERNATE DESIGN SUBMITTAL SHALL INCLUDE SHOP DRAWINGS AND/OR MATERIALS DATA AND MANUFACTURER'S RECOMMENDATIONS.
- 2. BULKBAGS SHALL BE FILLED WITH SAND. PLACE FILLED BULKBAGS ADJACENT TO ONE ANOTHER TO CREATE A CONTINUOUS ROW THAT ISOLATES THE WORK AREA FROM SURFACE FLOWS.
- 3. IF WATER DEPTH EXCEEDS 85% OF THE BULKBAG HEIGHT, AN ADDITIONAL TOP ROW OF BULKBAGS SHALL BE INSTALLED. SUPPORTED BY TWO BOTTOM ROWS OF BULKBAGS.
- 4. BULKBAG COFFERDAM SHALL BE SEALED BY COVERING THE COFFERDAM WITH PLASTIC SHEETING HELD IN PLACE BY STANDARD SANDBAGS PLACED IN ROWS ON TOP OF COFFERDAM, AND AT TOE OF COFFERDAM. THE PLASTIC SHEETING SHALL BE DRAPED ALONG THE CHANNEL BOTTOM ON THE WORK AREA SIDE OF THE COFFERDAM WITH OUTWARD EDGE OF SHEETING MINIMUM 4-FEET FROM TOE OF COFFERDAM. THE DRAPED PORTION OF PLASTIC SHEETING SHALL BE PINNED TO THE CHANNEL BED BY MINIMUM TWO ROWS OF STANDARD SANDBAGS.
- 5. THE OUTWARD EDGE OF PLASTIC SHEETING ON WORK AREA SIDE SHALL BE TOED INTO THE CHANNEL BED MINIMUM 1-FT. TOEING IN THE OUTWARD EDGE OF PLASTIC SHEETING SHALL OCCUR AFTER THE COFFERDAM IS CLOSED TO PREVENT TURBIDITY RELEASE TO THE WATERWAY.
- 6. THE COFFERDAM SHALL BE TIGHTLY SEALED TO THE GROUND BY PLASTIC SHEETING AND STANDARD SANDBAGS. MULTIPLE LAYERS OF SHEETING AND SANDBAGS MAY BE REQUIRED TO FORM A WATERTIGHT SEAL.
- 7. BULKBAGS SHALL BE WATERPROOF CUBE-SHAPED POLYPROPYLENE WOVEN FABRIC BAGS WITH FULLY OPEN TOP, FLAT BOTTOM, FOUR LOOPS, MINIMUM 2-TON WEIGHT CAPACITY, MINIMUM
- 8. PLASTIC SHEETING SHALL BE MINIMUM 6-MIL THICKNESS. ROLL LENGTH SHALL BE LONG ENOUGH TO ENSURE THAT ENTIRE LENGTH OF COFFERDAM WILL BE COVERED WITHOUT A SEAM. MINIMUM 12-FT WIDE ROLL SHALL BE USED FOR SINGLE LAYER BULK BAG COFFERDAM. MINIMUM 16-FT WIDE ROLL SHALL BE USED FOR 2-LAYER STACKED BULKBAG COFFERDAM.
- 9. CONTRACTOR SHALL PROVIDE PUMPING SUFFICIENT FOR A NET INFLOW TO THE WORK AREA, AND DISCHARGE TURBID WATER TO UPLAND FLOODPLAIN.
- 10. BULKBAG COFFERDAM SHALL BE COMPLETELY REMOVED AFTER CONSTRUCTION IS COMPLETED AND TURBIDITY HAS BEEN REMOVED.
- 11. IF NECESSARY, GAPS BETWEEN BULKBAGS MAY BE FILLED WITH BENTONITE TO SEAL AND IMPROVE COFFERDAM SEAL.



NOTE: CONTRACTOR MAY PROVIDE ALTERNATE DESIGN WITH EQUAL PERFORMANCE.



SCRAP 2 INCH BY 4 INCH-6", TYP. WORK-SIDE

PLAN VIEW

- THE INTENT OF THIS DETAIL IS TO PROTECT EXISTING TREES FROM DAMAGE DURING CONSTRUCTION.
- THIS TREE PROTECTION DETAIL SHALL BE USED WHEN DIRECTED BY OWNER.
- ALL TREES SHALL BE SAVED UNLESS NOTED OTHERWISE ON THE PLANS OR AS DIRECTED BY THE OWNER.
- LUMBER, WIRE, AND SANDBAGS MAY BE REUSED AT OTHER TREES, AS WORK PROGRESSES.
- CONTRACTOR MAY PROVIDE ALTERNATIVE DESIGN WITH EQUAL PERFORMANCE.




TYPICAL DETAIL: TREE PROTECTION

NOT TO SCALE














SCALE:	DATE: DRAWN:		CHECKED:
	11/17/23	RP	BN
PROJ. NO:	DRAWING NO:		Total Sheets:
l _	25		74














































CROSS-SECTION STA. 6+02




2 CROSS-SECTION STA. 7+08



3 CROSS-SECTION STA. 8+06


LEGEND




- PROPOSED GRADE

NOTE:

- ALL CROSS-SECTIONS ARE ORIENTED LEFT TO RIGHT LOOKING DOWNSTREAM.
- 2. CONTRACTOR SHALL ANTICIPATE
 AND ASSUME FIT-IN-THE-FIELD
 APPROACH TO CUTS AND FILLS
 WITHIN THE RESERVOIR FOOTPRINT
 BASED ON EXPOSED SURFACES
 AFTER RESERVOIR DRAWDOWN
 AND HABITAT GOALS.
- 3. AREA BETWEEN SONAR RETURN SURFACE GRADE AND PROPOSED GRADE IS A COMBINATION OF IMPOUNDED SEDIMENTS THAT NEED TO BE DEWATERED AND CHANNEL EXCAVATION.





3	-	-	-
2	-		-
1	-	1	-
REV:	DESCRIPTION:	BY:	DATE:
STATU	* FINAL DESIGN		








KWONEESUM DAM REMOVAL DESIGN


KWONEESUM RESERVOIR – EAST TRIB. GRADING CROSS-SECTIONS

SCALE:	DATE:	DRAWN:	CHECKED:
	11/17/23	RP	BN
PROJ. NO:	DRAWING NO:	•	Total Sheets:
_	_	41	l 74












CROSS-SECTION STA. 3+77



2 CROSS-SECTION STA. 4+77



3 CROSS-SECTION STA. 5+77



CROSS-SECTION STA. 6+77

LEGEND


_ . __ . __ SONAR RETURN SURFACE GRADE


ORDINARY HIGH WATER (OHW)

PROPOSED GRADE

NOTE:

- ALL CROSS-SECTIONS ARE ORIENTED LEFT TO RIGHT LOOKING DOWNSTREAM.
- 2. CONTRACTOR SHALL ANTICIPATE
 AND ASSUME FIT-IN-THE-FIELD
 APPROACH TO CUTS AND FILLS
 WITHIN THE RESERVOIR FOOTPRINT
 BASED ON EXPOSED SURFACES
 AFTER RESERVOIR DRAWDOWN
 AND HABITAT GOALS.
- 3. AREA BETWEEN SONAR RETURN SURFACE GRADE AND PROPOSED GRADE IS A COMBINATION OF IMPOUNDED SEDIMENTS THAT NEED TO BE DEWATERED AND CHANNEL EXCAVATION.





1	3	-	1	
1	2	-	-	-
	1	-	-	-
1	REV:	DESCRIPTION:	BY:	DATE:
		DESCRIPTION: S: FINAL DESIGN	BY:	DATE:








KWONEESUM DAM REMOVAL DESIGN


KWONEESUM RESERVOIR – WEST TRIB. GRADING CROSS-SECTIONS


SCALE:	DATE:	DRAWN:	CHECKED:
	11/17/23	RP	BN
PROJ. NO:	DRAWING NO:		Total Sheets:
	15		
_	/	15	7/
















KWONEESUM DAM REMOVAL DESIGN


KWONEESUM DAM -SPILLWAY CROSS-SECTIONS

SCALE:	DATE:	DRAWN:	CHECKED:
	11/17/23	RP	BN
PROJ. NO:	DRAWING NO:		Total Sheets:
-	∠	48	74

TYPICAL CROSS-SECTION: SPILLWAY FILL AND REGRADE

NOT TO SCALE






NOT TO SCALE


PROFILE VIEW: EPHEMERAL TRIBUTARY

NOTES:

CONTRACTOR SHALL PROVIDE 6 IN.
 MIN. THICKNESS OF TOPSOIL, TYPE B
 FOR ESTABLISHMENT OF NATIVE
 VEGETATION WITHIN THE RESERVOIR
 AND DAM FOOTPRINT.







3	-	-	-
2	-		-
1	-	1	-
REV:	DESCRIPTION:	BY:	DATE:






KWONEESUM DAM REMOVAL DESIGN

TITLE:

KWONEESUM RESERVOIR -EPHEMERAL TRIB. CROSS-SECTIONS

SCALE:	DATE:	DRAWN:	CHECKED:
	11/17/23	RP	BN
PROJ. NO:	DRAWING NO:		Total Sheets:
	l 5∩ l		
_		50	7⊿





1. ALL VOLUMES OF ON-SITE MATERIALS ARE APPROXIMATE.

LEGEND

— — LIMITS OF DISTURBANCE


TEMPORARY ACCESS

EXISTING GRADING

2. REUSE SORTED MATERIALS. CLASSIFIED AS COMMON FILL, SELECT BORROW, GRAVEL BORROW, AND BOULDERS. BOULDERS SHALL BE REUSED AS BALLAST FOR LARGE WOOD STRUCTURES. SELECT BORROW AND GRAVEL BORROW SHALL BE USED IN CHANNEL CONSTRUCTION. COMMON FILL SHALL BE MIXED WITH FINES EXCAVATED FROM THE BOTTOM OF THE RESERVOIR AND THEN SPREAD IN UPLAND AREAS OF THE FORMER RESERVOIR, DAM, AND SPILLWAY. SLASH SHALL BE INCORPORATED INTO LARGE WOOD STRUCTURES.

TABLE: ON-SITE STOCKPILE

#	NAME	APPROXIMATE VOLUME CY.
1	COMMON FILL	7250
2	SELECT BORROW (2"-6")	3900
3	GRAVEL BORROW (2"-MINUS)	2400
4	BOULDERS	300
5	SELECT BORROW (2"-6")	400
6	SELECT BORROW (6"-24")	830
7	SELECT BORROW (2"-6")	3107
8	SLASH	550
9	SLASH	350



3	-	-	-
2	-	,	-
1	-	-	-
REV:	DESCRIPTION:	BY:	DATE:
	DESCRIPTION: S: FINAL DESIGN	BY:	DATE:







KWONEESUM DAM REMOVAL DESIGN


TITLE:


ON-SITE STOCKPILE - PLAN VIEW AND QUANTITIES


SCALE:	DATE:	DRAWN:	CHECKED:
	11/17/23	RP	BN
PROJ. NO:	DRAWING NO:		Total Sheets:
_		51	74


























WILDBOY CREEK LARGE WOOD STRUCTURE QUANTITIES

Log Wood Structure: A				
Item	#	Unit		
Sill Logs	2	Pieces		
Logs	4	Pieces		
Rootwads	4	Pieces		
Rock Anchors	10	Connection		
Threaded Rod Length	106	FT		
Chain Connections Length	40	FT		
Nuts	42	Pieces		
Washers	42	Pieces		
Strawbales	52	Pieces		
Select Borrow	472	CY		
Streambed Substrate	163	CY		
Slash	70	CY		

Log Wood Structure: B				
Item	#	Unit		
Sill Logs	2	Pieces		
Logs	4	Pieces		
Rootwads	4	Pieces		
Rock Anchors	10	Connectio		
Threaded Rod Length	125	FT		
Chain Connections Length	40	FT		
Nuts	46	Pieces		
Washers	46	Pieces		
Strawbales	54	Pieces		
Select Borrow	266	CY		
Streambed Substrate	96	CY		
Slash	50	CY		
		-		

	#	Unit
Sill Logs	2	Pieces
Logs	4	Pieces
Rootwads	4	Pieces
Rock Anchors	10	Connections
Threaded Rod Length	123	FT
Chain Connections Length	40	FT
Nuts	46	Pieces
Washers	46	Pieces
Strawbales	54	Pieces
Select Borrow	279	СУ
Streambed Substrate	99	CY
Slash	80	CY

Item	#	Unit
Sill Logs	2	Pieces
Logs	4	Pieces
Rootwads	4	Pieces
Rock Anchors	8	Connections
Threaded Rod Length	100	FT
Chain Connections Length	32	FT
Nuts	40	Pieces
Washers	40	Pieces
Strawbales	47	Pieces
Select Borrow	198	CY
Streambed Substrate	73	CY
Slash	40	CY

Item	#	Unit
Sill Logs	2	Pieces
Logs	5	Pieces
Rootwads	3	Pieces
Rock Anchors	8	Connectio
Threaded Rod Length	96	FT
Chain Connections Length	32	FT
Nuts	41	Pieces
Washers	40	Pieces
Strawbales	42	Pieces
Select Borrow	199	CY
Streambed Substrate	72	CY
Slash	40	CY

Item	#	Unit
Sill Logs		2 Pieces
Logs		5 Piece
Rootwads		3 Piece
Rock Anchors		8 Conn
Threaded Rod Length	9	6 FT
Chain Connections Length	3	2 FT
Nuts	3	8 Piece
Washers	3	8 Piece
Strawbales	4	3 Piece
Select Borrow	13	4 CY
Streambed Substrate	4	8 CY
Slash	5	0 CY

Item	#	Unit
Sill Logs	2	Pieces
Logs	4	Pieces
Rootwads	4	Pieces
Rock Anchors	10	Connectio
Threaded Rod Length	117	FT
Chain Connections Length	40	FT
Nuts	48	Pieces
Washers	49	Pieces
Strawbales	40	Pieces
Select Borrow	180	СУ
Streambed Substrate	64	CY
Slash	60	CY

	Log Wood Structure: H				
]	Item	#	Unit		
	Sill Logs	1	Pieces		
	Logs	3	Pieces		
	Rootwads	3	Pieces		
s	Rock Anchors	6	Connections		
	Threaded Rod Length	67	FT		
	Chain Connections Length	24	FT		
	Nuts	26	Pieces		
	Washers	26	Pieces		
_	Strawbales	32	Pieces		
	Select Borrow	161	CY		
1	Streambed Substrate	57	CY		
]	Slash	30	CY		

Log Wood Structure: I			
#	Unit		
1	Pieces		
3	Pieces		
3	Pieces		
6	Connection		
65	FT		
24	FT		
26	Pieces		
26	Pieces		
41	Pieces		
160	CY		
57	CY		
40	CY		
	# 1 3 3 6 65 24 26 26 41 160 57		

Log Wood Structure: W

Sill Logs

Rootwads

Washers

Strawbales Select Borrov

Rock Anchors

Threaded Rod Length

Streambed Substrate

Chain Connections Length

Item	#	Unit
Sill Logs	1	Pieces
Logs	2	Pieces
Rootwads	4	Pieces
Rock Anchors	6	Connection
Threaded Rod Length	64	FT
Chain Connections Length	24	FT
Nuts	26	Pieces
Washers	26	Pieces
Strawbales	40	Pieces
Select Borrow	154	СУ
Streambed Substrate	55	CY
Slash	30	CY

Item	#	Unit
Sill Logs	2	Pieces
Logs	5	Pieces
Rootwads	5	Pieces
Rock Anchors	8	Connection
Threaded Rod Length	106	FT
Chain Connections Length	32	FT
Nuts	38	Pieces
Washers	38	Pieces
Strawbales	37	Pieces
Select Borrow	184	CY
Streambed Substrate	65	CY
Slash	50	CY

Log Wood Structure: R

Item

Logs

Rootwads

Washers

Strawbales

Rock Anchors

Threaded Rod Length

Streambed Substrate

Chain Connections Length

Item	#	Unit
Sill Logs	1	Pieces
Logs	2	Pieces
Rootwads	4	Pieces
Rock Anchors	6	Connection
Threaded Rod Length	69	FT
Chain Connections Length	24	FT
Nuts	28	Pieces
Washers	28	Pieces
Strawbales	47	Pieces
Select Borrow	147	CY
Streambed Substrate	51	CY
Slash	40	CY

Log Wood Structure: S

1 Pieces

3 Pieces

3 Pieces

58 FT

24 FT

24 Pieces

24 Pieces

40 Pieces

185 CY

65 CY

6 Connections

Logs

Rootwads

Washers

Slash

Strawbales

Select Borrow

Streambed Substrate

Rock Anchors

Threaded Rod Length

Chain Connections Length

Item

Logs

Nuts

Washers

Strawbales

Select Borrow

Streambed Substrate

Rootwads

Rock Anchors

Threaded Rod Length

Chain Connections Length

6 Pieces

1 Pieces

97 FT

32 FT

38 Pieces

38 Pieces

47 Pieces

124 CY

8 Connections

Item	#	Unit
Sill Logs	1	Pieces
Logs	2	Pieces
Rootwads	4	Pieces
Rock Anchors	6	Connection
Threaded Rod Length	64	FT
Chain Connections Length	24	FT
Nuts	22	Pieces
Washers	22	Pieces
Strawbales	47	Pieces
Select Borrow	146	CY
Streambed Substrate	54	CY
Slash	40	CY

Log Wood Structure: T

Log Wood Structu	ıre: N	
Item	#	Unit
Sill Logs	2	Pieces
Logs	4	Pieces
Rootwads	4	Pieces
Rock Anchors	10	Connecti
Threaded Rod Length	99	FT
Chain Connections Length	40	FT
Nuts	40	Pieces
Washers	40	Pieces
Strawbales	34	Pieces
Select Borrow	293	CY
Streambed Substrate	103	CY
Slash	50	CY
1		

Log Wood Structure: U

Pieces

5 Pieces

2 Pieces

65 FT

26 Pieces

26 Pieces

47 Pieces

76 CY

Logs

Rootwads

Strawbales

Select Borrow

Streambed Substrate

Rock Anchors

Threaded Rod Length

Chain Connections Length

Item

Logs

Nuts

Slash

Washers

Strawbales

Select Borrow

Streambed Substrate

1 Pieces

4 Pieces

2 Pieces

67 FT

24 FT

26 Pieces

26 Pieces

47 Pieces

70 CY

6 Connections

Sill Logs

Rootwads

Rock Anchors

Threaded Rod Length

Chain Connections Length

Log Wood Structure: O					
Item	#	Unit			
Sill Logs	2	Pieces			
Logs	3	Pieces			
Rootwads	5	Pieces			
Rock Anchors	10	Connection			
Threaded Rod Length	95	FT			
Chain Connections Length	40	FT			
Nuts	38	Pieces			
Washers	38	Pieces			
Strawbales	47	Pieces			
Select Borrow	288	CY			
Streambed Substrate	103	CY			
Slash	100	CY			

Log Wood Structure: V

Pieces

4 Pieces

2 Pieces

54 FT

16 FT

22 Pieces

22 Pieces

47 Pieces

264 CY

94 CY

JULIAM JULIAN JULIAN	P. NORPO
POR SION	576 O ES STERED ES

	3SIONAL EN
3	-
2	-
1	-
REV:	DESCRIPTION:
STATU	S: FINAL DESIGN

PA	
302 W. Steuben St. #6	
Bingen, WA 98605	www.ers4life.com

CLIENT:	
	COWLITZ INDIAN TRIBE
	7700 26TH AVE
	VANCOUVER, WA, 98665
	77 (11CCO TER, 1171, 70000

CLIENT:	WLITZ INDIAN	TRIBE
	26TH AVE	
VANC	COUVER, WA, 98665	
A CONTRACTOR OF THE PROPERTY O		

SITE:	KWONEESUM DAM
	REMOVAL DESIGN

	_		
TTLE:			
WII DBC	Y CRE	FK - I (OG L

SCALE:	DATE:	DRAWN:	CHECKED:
	11/17/23	RP	BN
PROJ. NO:	DRAWING NO:	•	Total Sheets
_	/	(2	7/

QUANTITIES

og Wood Structu	ro. D		Log Wood Structu	ıra. O	
Log Wood Structure: P		Log Wood Structure: Q			
em	#	Unit	Item	#	Unit
ill Logs	4	Pieces	Sill Logs	2	Pieces
ogs	12	Pieces	Logs	4	Pieces
ootwads	3	Pieces	Rootwads	4	Pieces
ock Anchors	16	Connections	Rock Anchors	8	Connection
hreaded Rod Length	211	FT	Threaded Rod Length	91	FT
hain Connections Length	64	FT	Chain Connections Length	32	FT
uts	82	Pieces	Nuts	36	Pieces
Vashers .	82	Pieces	Washers	36	Pieces
trawbales	47	Pieces	Strawbales	47	Pieces
elect Borrow	540	CY	Select Borrow	225	CY
treambed Substrate	185	CY	Streambed Substrate	82	CY
lash	140	CY	Slash	80	CY

1 Pieces 5 Pieces

1 Pieces

77 FT

32 FT

36 Pieces 37 Pieces

47 Pieces

240 CY 83 CY

Item	#	Unit
Sill Logs	1	Pieces
Logs	4	Pieces
Rootwads	2	Pieces
Rock Anchors	8	Connections
Threaded Rod Length	92	FT
Chain Connections Length	32	FT
Nuts	38	Pieces
Washers	38	Pieces
Strawbales	44	Pieces
Select Borrow	121	СУ
Streambed Substrate	47	CY
Slash	60	CY

Log Wood Structure: Y					
#	Unit				
1	Pieces				
2	Pieces				
4	Pieces				
8	Connections				
83	FT				
32	FT				
34	Pieces				
34	Pieces				
47	Pieces				
155	CY				
56	CY				
50	CY				
	# 1 2 4 8 83 32 34 34 47 155 56				


Item	#	Unit
Sill Logs	3	Pieces
Logs	8	Pieces
Rootwads	3	Pieces
Rock Anchors	12	Connections
Threaded Rod Length	151	FT
Chain Connections Length	48	FT
Nuts	58	Pieces
Washers	58	Pieces
Strawbales	47	Pieces
Select Borrow	323	CY
Streambed Substrate	115	CY
Slash	70	CY

Log Wood Structu	ıre: AA	
Item	#	Unit
Sill Logs	1	Pieces
Logs	3	Pieces
Rootwads	3	Pieces
Rock Anchors	6	Connections
Threaded Rod Length	63	FT
Chain Connections Length	24	FT
Nuts	24	Pieces
Washers	24	Pieces
Strawbales	47	Pieces
Select Borrow	159	CY
Streambed Substrate	57	CY
Slash	40	CY


	Log Wood Structu	ıre: AB	
	Item	#	Ur
	Sill Logs	1	Pie
	Logs	3	Pie
	Rootwads	3	Pie
s	Rock Anchors	6	Со
	Threaded Rod Length	62	FT
	Chain Connections Length		FT
	Nuts	24	Pie
	Washers	24	Pie
	Strawbales	47	Pie
	Select Borrow	170	CY
	Streambed Substrate	63	CY
	Slash	20	CY


Log Wood Structu	re: AB		Log
Item	#	Unit	Item
Sill Logs	1	Pieces	Sill Log
Logs	3	Pieces	Logs
Rootwads	3	Pieces	Rootwa
Rock Anchors	6	Connections	Rock A
Threaded Rod Length	62	FT	Thread
Chain Connections Length		FT	Chain C
Nuts	24	Pieces	Nuts
Washers	24	Pieces	Washe
Strawbales	47	Pieces	Strawb
Select Borrow	170	CY	Select I
Streambed Substrate	63	CY	Stream
Slash	20	CY	Slash


ture: AB			Log Wood Structu	ıre: AC	
	#	Unit	Item	#	Unit
	1	Pieces	Sill Logs	2	Pieces
	3	Pieces	Logs	4	Pieces
	3	Pieces	Rootwads	4	Pieces
	6	Connections	Rock Anchors	10	Connections
	62	FT	Threaded Rod Length	98	FT
1		FT	Chain Connections Length	40	FT
	24	Pieces	Nuts	36	Pieces
	24	Pieces	Washers	36	Pieces
	47	Pieces	Strawbales	47	Pieces
	170	CY	Select Borrow	165	CY
	63	CY	Streambed Substrate	63	CY











SILL LOG

EXISTING GROUND

EXISTING NATIVE MATERIAL

LOG (WITH OR WITHOUT ROOTWAD, AS SHOWN ON PREVIOUS SHEETS OR AS DIRECTED BY OWNER)


STRAWBALES


STREAMBED SUBSTRATE

SALVAGED TEMPORARY ACCESS ROAD MATERIAL

PACKED SLASH

- SPECIFIC LOCATION, ALIGNMENT, AND ELEVATIONS OF LARGE WOOD PIECES, BOULDERS ARE SUBJECT TO CHANGE BASED ON FIELD CONDITIONS, MATERIAL SIZE AND STABILITY REQUIREMENTS.
- 2. ALL CROSS-SECTIONS ARE ORIENTED LEFT TO RIGHT LOOKING DOWNSTREAM.
- 3. CONTRACTOR SHALL ANTICIPATE AND ASSUME OWNER-DIRECTED FIT-IN-THE-FIELD APPROACH TO STREAM **RESTORATION TASKS WITHIN WILDBOY** CREEK. REQUIRES HIGHLY QUALIFIED **HEAVY EQUIPMENT OPERATORS** WELL-VERSED IN CONSTRUCTION OF LARGE WOOD STRUCTURES WHO ARE FLEXIBLE AND ADAPTABLE.





3	-	-	-
2	-	-	-
1	-	-	-
REV:	DESCRIPTION:	BY:	DATE:
STATU	S: FINAL DESIGN		








KWONEESUM DAM REMOVAL DESIGN


WILDBOY CREEK - TYPICAL LARGE WOOD **CROSS-SECTIONS**


11/17/23 RP 63














EXISTING GROUND

SILL LOG

EXISTING NATIVE MATERIAL

LOG (WITH OR WITHOUT ROOTWAD, AS SHOWN ON PREVIOUS SHEETS OR AS DIRECTED BY OWNER)

STREAMBED SUBSTRATE


SALVAGED TEMPORARY ACCESS ROAD MATERIAL


PACKED SLASH

STRAWBALES

NOT

- 1. SPECIFIC LOCATION, ALIGNMENT, AND
 ELEVATIONS OF LARGE WOOD PIECES, BOULDERS
 ARE SUBJECT TO CHANGE BASED ON FIELD
 CONDITIONS, MATERIAL SIZE AND STABILITY
 REQUIREMENTS.
- 2. ALL CROSS-SECTIONS ARE ORIENTED LEFT TO RIGHT LOOKING DOWNSTREAM.
- 3. CONTRACTOR SHALL ANTICIPATE AND ASSUME OWNER-DIRECTED FIT-IN-THE-FIELD APPROACH TO STREAM RESTORATION TASKS WITHIN WILDBOY CREEK. REQUIRES HIGHLY QUALIFIED HEAVY EQUIPMENT OPERATORS WELL-VERSED IN CONSTRUCTION OF LARGE WOOD STRUCTURES WHO ARE FLEXIBLE AND ADAPTABLE.





3	-	-	-
2	-	-	-
1	-	-	1
REV:	DESCRIPTION:	BY:	DATE:
STATU	FINAL DESIGN		








KWONEESUM DAM REMOVAL DESIGN


WILDBOY CREEK - TYPICAL LARGE WOOD CROSS-SECTIONS

SCALE:	DATE:	DRAWN:	CHECKED:
	11/17/23	RP	BN
PROJ. NO:	DRAWING NO:		Total Sheets:
-	(54	74











SILL LOG

EXISTING GROUND

EXISTING NATIVE MATERIAL

LOG (WITH OR WITHOUT ROOTWAD, AS SHOWN ON PREVIOUS SHEETS OR AS DIRECTED BY OWNER)

STREAMBED SUBSTRATE


SALVAGED TEMPORARY ACCESS ROAD MATERIAL


PACKED SLASH

STRAWBALES

NOTE:

- 1. SPECIFIC LOCATION, ALIGNMENT, AND ELEVATIONS OF LARGE WOOD PIECES, **BOULDERS ARE SUBJECT TO CHANGE** BASED ON FIELD CONDITIONS, MATERIAL SIZE AND STABILITY REQUIREMENTS.
- 2. ALL CROSS-SECTIONS ARE ORIENTED LEFT TO RIGHT LOOKING DOWNSTREAM.
- 3. CONTRACTOR SHALL ANTICIPATE AND ASSUME OWNER-DIRECTED
 FIT-IN-THE-FIELD APPROACH TO STREAM RESTORATION TASKS WITHIN WILDBOY CREEK. REQUIRES HIGHLY QUALIFIED **HEAVY EQUIPMENT OPERATORS** WELL-VERSED IN CONSTRUCTION OF LARGE WOOD STRUCTURES WHO ARE FLEXIBLE AND ADAPTABLE.





3	-	-	-
2	-	-	-
1	-	-	-
REV:	DESCRIPTION:	BY:	DATE:
	DESCRIPTION: S: FINAL DESIGN	BY:	DATE:








KWONEESUM DAM REMOVAL DESIGN


WILDBOY CREEK - TYPICAL LARGE WOOD **CROSS-SECTIONS**


11/17/23 RP 65











EXISTING GROUND

SILL LOG

EXISTING NATIVE MATERIAL

LOG (WITH OR WITHOUT ROOTWAD, AS SHOWN ON PREVIOUS SHEETS OR

AS DIRECTED BY OWNER)


STREAMBED SUBSTRATE


SALVAGED TEMPORARY ACCESS **ROAD MATERIAL**

PACKED SLASH

STRAWBALES

- SPECIFIC LOCATION, ALIGNMENT, AND ELEVATIONS OF LARGE WOOD PIECES, BOULDERS ARE SUBJECT TO CHANGE BASED ON FIELD CONDITIONS, MATERIAL SIZE AND STABILITY REQUIREMENTS.
- 2. ALL CROSS-SECTIONS ARE ORIENTED LEFT TO RIGHT LOOKING DOWNSTREAM.
- 3. CONTRACTOR SHALL ANTICIPATE AND ASSUME OWNER-DIRECTED FIT-IN-THE-FIELD APPROACH TO STREAM RESTORATION TASKS WITHIN WILDBOY CREEK. REQUIRES HIGHLY QUALIFIED HEAVY EQUIPMENT OPERATORS
 WELL-VERSED IN CONSTRUCTION OF LARGE WOOD STRUCTURES WHO ARE FLEXIBLE AND ADAPTABLE.





3	-	-	-
2	-	-	-
1	-	-	-
REV:	DESCRIPTION:	BY:	DATE:
	DESCRIPTION: S: FINAL DESIGN	BY:	DATE:







KWONEESUM DAM REMOVAL DESIGN

WILDBOY CREEK - TYPICAL LARGE WOOD **CROSS-SECTIONS**

SCALE:	DATE:	DRAWN:	CHECKED:
	11/17/23	RP	BN
PROJ. NO:	DRAWING NO:		Total Sheets:
-	6	66	74






THREADED ROD EMBEDDED 12 IN. MIN. ADHERE

(SEE SPECIAL PROVISIONS).

WITH EPOXY, STEEL WASHER AND NUT FASTENERS,


- SPECIFIC LOCATION, ALIGNMENT AND ELEVATIONS OF LARGE WOOD PIECES, BOULDERS AND ASSOCIATED MATERIALS ARE SUBJECT TO CHANGE BASED ON FIELD CONDITIONS, MATERIAL SIZE AND STABILITY REQUIREMENTS. CONTRACTOR SHALL ANTICIPATE AND ASSUME OWNER-DIRECTED FIT-IN-THE-FIELD APPROACH TO STREAM RESTORATION TASKS WITHIN WILDBOY CREEK. REQUIRES HIGHLY QUALIFIED HEAVY EQUIPMENT OPERATORS WELL-VERSED IN CONSTRUCTION OF LARGE WOOD STRUCTURES WHO ARE FLEXIBLE AND ADAPTABLE.
- 2. IF COMPETENT BEDROCK IS NOT PRESENT WHERE SILL LOG OR OTHER LOGS ARE TO BE INSTALLED. CONTRACTOR SHALL INSTALL LARGE WOOD SINGLE BOULDER BALLAST WITH CHAIN OR LARGE WOOD BOULDER BALLAST WITH CHAIN (E.G., BOULDER-PAIR) AND/OR LARGE WOOD BOULDER BALLAST AS DIRECTED BY OWNER. SEE DETAILS ON SHEET 71.
- CONTRACTOR SHALL ANTICIPATE THE ORIENTATION OF THREADED RODS THROUGH LOGS WILL VARY. INTENT IS TO PROVIDE SUFFICIENT PURCHASE THROUGH LARGE WOOD. CONTRACTOR MAY PROPOSE SUBSTITUTING CHAIN FOR THREADED ROD SUBJECT TO OWNER APPROVAL




L	3	-	-	-
L	2	-	-	-
	1	-	1	-
	REV:	DESCRIPTION:	BY:	DATE:







TYPICAL SECTION: CHANNEL SPANNING LARGE WOOD STRUCTURES



NOT TO SCALE


ANCHORING IN WILDBOY CREEK


EXISTING BED

ROCK CHANNEL


EXISTING BED

ROCK CHANNEL





<u>PLAN VIEW</u> PLAN VIEW






NOT TO SCALE

TYPICAL DETAIL: LARGE WOOD TO LARGE WOOD ANCHORING TO BEDROCK



TYPICAL DETAIL: LARGE WOOD TO LARGE WOOD ANCHORING

NOT TO SCALE




3	-	-	-
2	-	-	-
1	-	-	
REV:	DESCRIPTION:	BY:	DATE:
STATUS: FINAL DESIGN			






	TYPI	CAL DETA	AILS
TITLE:			
	REMO	OVAL DES	IGN
SITE:	KWO	neesum [MAC

SCALE:	DATE: DRAWN:		CHECKED:
	11/17/23	RP	BN
PROJ. NO:	DRAWING NO:		Total Sheets:
_	70		74




TYPICAL DETAIL: LARGE WOOD BOULDER BALLAST
NOT TO SCALE




TYPICAL DETAIL: LARGE WOOD BOULDER BALLAST WITH CHAIN

NOT TO SCALE




PLAN VIEW



SECTION VIEW

TYPICAL DETAIL: LARGE WOOD SINGLE BOULDER BALLAST WITH CHAIN


NOT TO SCALE




3	-	-	-
2	-	-	-
1	-	-	-
REV:	DESCRIPTION:	BY:	DATE:
	DESCRIPTION: St FINAL DESIGN	BY:	DATE:









SCALE:	DATE:	DRAWN:	CHECKED:
	11/17/23	RP	BN
PROJ. NO:	DRAWING NO:		Total Sheets:
-	71		74







TYPICAL DETAIL: SILL LOGS IN TRIBUTARIES

ORIENTATION TO BE ADJUSTED BASED ON

FIELD CONDITIONS


NOTES:

- 1. SPECIFIC LOCATION, ALIGNMENT AND ELEVATIONS OF LARGE WOOD PIECES, BOULDERS AND ASSOCIATED MATERIALS ARE SUBJECT TO CHANGE BASED ON FIELD CONDITIONS, MATERIAL SIZE AND STABILITY REQUIREMENTS. CONTRACTOR SHALL ANTICIPATE AND ASSUME OWNER-DIRECTED FIT-IN-THE-FIELD APPROACH TO STREAM RESTORATION TASKS WITHIN TRIBUTARIES. REQUIRES HIGHLY QUALIFIED HEAVY **EQUIPMENT OPERATORS** WELL-VERSED IN CONSTRUCTION OF LARGE WOOD STRUCTURES WHO ARE FLEXIBLE AND ADAPTABLE.
- 2. FLOODPLAIN WOOD MAY HAVE ROOTWADS ATTACHED DEPENDING ON AVAILABILITY AND OWNER DIRECTION.


TYPICAL PLAN: FLOODPLAIN WOOD NOT TO SCALE

FINISHED GRADE-

NOT TO SCALE


















Notes:



SHEET LOCATION



	STATUS: FINAL DESIGN			
	REV:	DESCRIPTION:	BY:	DATE:
	1	=		-
1	2	=		-
	3	-	-	-





KWONEESUM DAM REMOVAL DESIGN

KWONEESUM RESERVOIR AND WILDBOY CREEK -SEEDING PLAN

RES)	SCALE:	DATE:	DRAWN:	CHECKED:	
(LJ)		11/17/23	RP	BN	
\FC\	PROJ. NO:	DRAWING NO:		Total Sheets:	
RES)	-	74		74	